HydroBID Flood Tutorials

Flood Modeling System

August 2026

Hydronia LLC

OilFlow2D™, RiverFlow2D™ models, and documentation produced by Hydronia, LLC, Pembroke Pines, FL. USA.
Information in this document is subject to change without notice and does not represent a commitment on part of Hydronia, LLC. The software described in this document is furnished under a license agreement.
RiverFlow2D, OilFlow2D, RiverFlow2D, and RiverFlow2D GPU are copyrighted by Hydronia, LLC. 2011-2026.
OilFlow2D™ and RiverFlow2D™ are registered trademarks of Hydronia, LLC.
All other products or service names mentioned herein are trademarks of their respective owners.
All rights reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means electronic, mechanical, photocopying, recording or otherwise, without the prior written permission of Hydronia, LLC.
Last document modification date: August 2026.
Technical Support: support@hydronia.com
Web site: www.hydronia.com

Content

List of Figures vii

1 Introduction 1

2 Creating your first HydroBID Flood application 2
2.1 Starting a new project . . . 2
2.2 Start a new project . . . 4
2.3 Load elevation data . . . 6
2.4 Create the limits of the modeling area . . . 8
2.5 Generating the triangular-cell mesh . . . 10
2.6 Setting up the boundary conditions . . . 11
2.7 Assigning Manning's . . . 13
2.8 Exporting the files . . . 15

3 Multiple Scenario Project Tool 18
3.1 New interface elements for managing multi-scenario projects in HydroBID Flood . . . 18
3.2 Creating a new HydroBID Flood multiple-scenario project using QGIS . . . 19
3.3 Create a new scenario . . . 20
3.4 Switching scenarios . . . 21
3.5 Deleting scenarios . . . 22
3.6 Import an HydroBID Flood project into Multi-scenario mode . . . 22

4 Simulating levees using weirs 24
4.1 Open an existing project . . . 25
4.2 Create a Weirs layer and the weir polyline . . . 25
4.3 Generate the mesh . . . 28
4.4 Exporting files to HydroBID Flood . . . 29
4.5 Running the model . . . 31
4.6 Review the output files . . . 32

5 Simulating bridges 34
5.1 Create a bridge geometry file . . . 34
5.2 Open an existing project . . . 37
5.3 Enter the bridge polyline in the *Bridges* layer . . . 37
5.4 Generate the mesh . . . 40
5.5 Exporting files to HydroBID Flood . . . 40
5.6 Running the Model . . . 42

6 Simulating culverts **46**
6.1 Open an existing project . . . 48
6.2 Create Culverts layer and draw the culvert . . . 48
6.3 Generate the mesh . . . 51
6.4 Exporting files to HydroBID Flood . . . 51
6.5 Running the model . . . 53
6.6 Review culvert output file . . . 55

7 Simulating dam breaches **57**
7.1 Open an existing project . . . 57
7.2 Create the DamBreach layer and draw the line that defines the dam . . . 58
7.3 Generate the mesh . . . 61
7.4 Exporting files to HydroBID Flood . . . 62
7.5 Running the model . . . 63
7.6 Review the output files . . . 67

8 Establishing initial water, mud, or tailings elevations **68**
8.1 Open an existing HydroBID Flood project . . . 68
8.2 Importing the Initial WSE raster layer . . . 69
8.3 Exporting files to HydroBID Flood . . . 70

9 Simulating bed load sediment transport with limited erosion bed areas **72**
9.1 Open an existing project . . . 72
9.2 Add MaximumErosionDepth layer and draw the polygon that defines the area of limited erosion . . . 73
9.3 Generate the mesh . . . 76
9.4 Exporting files to HydroBID Flood . . . 77
9.5 Running the model . . . 79
9.6 Check the output files . . . 81

10 Simulating suspended sediment transport with inflows of suspended sediment concentrations **83**
10.1 Open an existing project . . . 83
10.2 Exporting files to HydroBID Flood . . . 84
10.3 Running the model . . . 85
10.4 Check the output files . . . 89
10.5 Generate a Concentration Map . . . 89

11 Hydrologic simulations **91**
11.1 Create the rainfall and evaporation time series data file . . . 91
11.2 Create the infiltration parameters data file . . . 92
11.3 Open an existing project . . . 93
11.4 Add the *RainEvap* component layer, and the rainfall/evaporation polygons . . . 93
11.5 Add the *Infiltration* component layer, and the Infiltration polygons . . . 95
11.6 Generate the mesh . . . 99
11.7 Exporting files to HydroBID Flood . . . 100

11.8 Running the model . . . 101
11.9 Utilizing the Cross Section Tool to review output files . . . 104

12 Urban Drainage using HydroBID Flood and EPA-SWMM 106
12.1 Storm drain configuration in EPA-SWMM . . . 108
12.1.1 Starting QGIS . . . 116
12.1.2 Start a new HydroBID Flood project . . . 117
12.1.3 Load elevation data . . . 119
12.1.4 Import the surface-storm drain exchange node connections from the SWMM .INP file . . . 121
12.1.5 Create the limits of the modeling area . . . 122
12.1.6 Assigning Manning's n . . . 124
12.1.7 Imposing the boundary conditions . . . 125
12.1.8 Generating the triangular-cell mesh . . . 126
12.2 Exporting the files . . . 127

13 Simulating a tailings dam failure with HydroBID Flood MT 132
13.1 Start a new project for a tailing dam break simulation . . . 133
13.2 Load elevation data . . . 134
13.3 Create the limits of the modeling area . . . 137
13.4 Create more detail for the mesh down the main flow area . . . 138
13.5 Generating the triangular-cell mesh . . . 140
13.6 Setting up the boundary conditions . . . 141
13.7 Assigning Manning's n . . . 145
13.8 Providing the Initial Concentrations for the tailings material . . . 146
13.9 Exporting the project from QGIS to HydroBID Flood . . . 147
13.10 Configure final model parameters in the Hydronia Data Input Program (DIP). . . . 149
13.10.1 Control Data Panel . . . 149
13.10.2 Mud/Tailings Flow Panel . . . 150
13.10.3 Providing the Viscosity and Yield Stress data for Variable properties-Erosion-Deposition Model . . . 151
13.10.4 Updating the Inflow Boundary Condition File . . . 152
13.11 Running the model . . . 153
13.12 Generating maps for the Mud/Tailings Flow module . . . 153
13.13 Generating animations for the Mud/Tailings Flow module . . . 155

14 Simulating Pollutant Transport 157
14.1 Create a scenario to model a single pollutant as an initial condition . . . 158
14.2 Create an Initial Concentrations layer. . . . 158
14.3 Enter pollutant data. . . . 160
14.4 Generate the mesh and Export to HydroBID Flood . . . 161
14.5 Review Boundary Condition Panel for Pollutant Inflow . . . 164
14.6 Review the output files . . . 165
14.7 Create a second scenario for adding a new pollutant source under existing conditions 167
14.8 Adding required multiple pollutants concentrations information . . . 169

14.9 Add the new pollutant parameters in the Hydronia Data Input Program then Run the HydroBID Flood model . . . 171

15 Wind driven circulation 176
15.1 Open an existing project . . . 176
15.2 Wind velocity time-series data file . . . 177
15.3 Create the template for the wind layer and the wind speed polygons . . . 178
15.4 Generate the mesh . . . 180
15.5 Exporting files . . . 181
15.6 Running the model . . . 183
15.7 Check the wind output files . . . 185

16 Using Manning's n ESRI shape files 187
16.1 Open an existing project . . . 187
16.2 Load the shape file with the Manning's n polygons . . . 188
16.3 Import the Manning's n geometry and values to the Manning N layer . . . 189

17 Post-processing calculations 193
17.1 Open an existing project . . . 193
17.2 Create a template of the layers *ObservationPoints*, *CrossSections* and *Profiles* and draw the output controls . . . 194
17.3 Generate the mesh . . . 199
17.3.1 Exporting files to HydroBID Flood . . . 200
17.4 Running the Model . . . 202
17.5 Review the output files . . . 203

18 Advanced digitization/snapping 207
18.1 Open an existing project . . . 208
18.2 Activate and configure the Snapping tool . . . 208
18.3 Draw contiguous or adjacent polygons using the Snapping tool . . . 209
18.4 Delete a polygon . . . 215

19 Creating raster elevations from X Y Z data sets 217

20 Setting up a Google Cloud VM for GPU-Accelerated Simulations 224
20.1 Before you begin . . . 224
20.1.1 Checking and Requesting GPU Quotas . . . 225
20.2 Creating the VM Instance . . . 225
20.3 Configuring Machine and GPU . . . 225
20.4 Configuring the Boot Disk and Firewall . . . 227
20.5 Create the VM and Handle Quota Requests . . . 228
20.6 Connect to the VM . . . 231

21 Creating high-impact graphics and animations using Paraview 232
21.1 Paraview basics . . . 232
21.2 Two-dimensional (2D) visualizations . . . 234
21.2.1 Create a 2D bed elevation map . . . 234

21.2.2 Creating 2D velocity vector fields 236
21.3 Three-dimensional (3D) visualizations 240
21.3.1 Create a 3D water elevation graphic adding a (h+z) layer 245
21.3.2 Create a velocity field graphic 247
21.4 Generating animations 249
21.5 Streamlines representation 250

List of Figures

2.1 Files with data required for the example. . . . 2
2.2 QGIS interface indicating window areas. . . . 3
2.3 Plugins window showing standalone HydroBID Flood activated (pre-v10/standalone). 3
2.4 QGIS Plugins window showing Hydronia2DMS installed for version 10 and later. . 4
2.5 Domain Outline layer. . . . 9
2.6 Resulting mesh. . . . 10
2.7 Message panel of the registry with GMSH messages. . . . 10

3.1 Drop-down list for displaying and selecting project scenarios . . . 18
3.2 Tool to create a new scenario within the project . . . 19
3.3 Tool to convert existing project to multi-scenario . . . 19
3.4 Menu to create a new project . . . 19
3.5 Dialog window to create a new HBF project . . . 20
3.6 Menu button to delete a scenario. . . . 22

4.1 The weir polyline representing the levee is shown in red. . . . 24
4.2 QGIS DIP Control Data panel for the Weirs tutorial. . . . 31
4.3 Extract of the output file of the Weir1. . . . 33

5.1 Data of the bridge geometry. . . . 36
5.2 Bridge hydrograph file '.bridgeh'. . . . 45

6.1 Culvert scheme. . . . 46
6.2 Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown. . . . 52
6.3 QGIS DIP Culverts component panel. . . . 54
6.4 Legacy Classic DIP Culverts component data panel. . . . 54
6.5 Culvert1 output file. . . . 56

7.1 QGIS DIP Dam Breach component panel. . . . 64
7.2 Legacy Classic DIP Dam Breach component. . . . 65

8.1 Project screen loaded in QGIS. . . . 69

9.1 Maps of elevation difference of the river bed between the initial time and at the end of the run. . . . 82

10.1 Project screen loaded in QGIS. . . . 84

10.2 Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown. . . . 85
10.3 QGIS DIP Control Data panel for suspended sediment transport. . . . 86
10.4 Legacy Classic DIP Control data panel. . . . 86
10.5 Map of suspended sediment concentration for the last time step. . . . 90

12.1 Inflow hydrograph applied at upstream end of storm drain. . . . 107
12.2 Storm drain profile. . . . 108
12.3 QGIS interface. . . . 117
12.4 Domain Outline layer. . . . 123
12.5 Polygon that covers the nodes defining the Outflow boundary condition segment. . . . 125
12.6 Resulting mesh. . . . 127

13.1 Files with data required for the example. . . . 132
13.2 Triangular mesh generated for the tailings dam break tutorial. . . . 141
13.3 Results map of Conc_1 at hour 2. . . . 155

14.1 Concentrations map for Conc_2 in scenario MultiplePollutant. . . . 174

15.1 QGIS DIP Wind component panel. . . . 184
15.2 Model window. . . . 185
15.3 Map with the speed field for the time 20 hours. . . . 186

16.1 Attribute table of the Manning N layer. . . . 192

18.1 Areas with overlap and empty spaces in manual digitization of adjacent polygons. . . . 207
18.2 Project screen loaded in QGIS. . . . 208
18.3 Snapping configuration panel. . . . 209

19.1 File containing terrain elevation points. . . . 217
19.2 Window to change the render style of a raster layer. . . . 222
19.3 Digital elevation model with color render. . . . 223

20.1 Configuring the machine with a custom N1 type, 4 vCPUs, 32 GB of memory, and one NVIDIA V100 GPU. . . . 227

21.1 Main Paraview window. . . . 233
21.2 View after opening the 'BridgeTutorial..vtk' file. . . . 233
21.3 VCR and Time Control toolbars. . . . 234
21.4 View for Time = 2. . . . 234
21.5 Variable selector. . . . 235
21.6 Bed elevation z representation. . . . 235
21.7 Predefined color maps. . . . 236
21.8 Bed elevation z representation. . . . 236
21.9 XRay Color Map. . . . 237
21.10 White-to-blue color map. . . . 237
21.11 White-to-blue color map. . . . 238

21.12 Water depth (h). 238
21.13 Velocity vector field on water depth. 239
21.14 Velocity vector field detail. 240
21.15 Bed elevation z. 241
21.16 Viewpoint Toolbar. 244
21.17 Alternative 3D bed elevation representation. 245
21.18 Camera Control Toolbar. 245
21.19 Water surface elevation representation. 246
21.20 Threshold Filter application. 247
21.21 Three dimensional water depth h representation. 247
21.22 Three-dimensional velocity field representation. 249
21.23 Animation. 249
21.24 StreamLines representation. 251

1 | Introduction

This document presents HydroBID Flood instructional material and tutorials to facilitate the application of several model components using QGIS. HydroBID Flood is based on Hydronia's RiverFlow2D engine and is tailored for HydroBID flood-risk and urban-drainage workflows.

HydroBID Flood is a combined hydrologic and hydrodynamic finite-volume model for rivers, estuaries, coastal areas, and floodplains. It can simulate floods and inundation over complex terrain at high resolution and with remarkable stability, accuracy, and speed. The use of adaptive triangular-cell meshes enables the flow field to be resolved around key features in difficult river environments.

Hydronia computational engines use an accurate, fast, and stable finite-volume solution method that eliminates the boundary and hot start difficulties of some two-dimensional flexible mesh models. HydroBID Flood can represent dam or levee breaches and can integrate hydraulic structures such as culverts, weirs, bridges, and gates. The hydrologic capabilities include spatially distributed rainfall, evaporation, and infiltration. This current version can integrate the effect of spatially distributed wind stresses on the water surface.

The user interface of Hydronia models is based on QGIS, a powerful software for the analysis of geographic information systems of free distribution. This software system integrated with GMSH mesh generation plugin provides interactive functions to generate and refine the finite-volume flexible mesh, and uses familiar GIS objects to construct a high level representation of the model. QGIS also offers a complete set of visualization tools that include rendering, for the representation of the results generated by the model.

2 | Creating your first HydroBID Flood application

This section provides a step-by-step guide to help you get started with a HydroBID Flood project using the QGIS interface. The example illustrates the model application to simulate flow in a river with a single inflow upstream and a single outflow downstream. It includes instructions to enter the terrain elevation data, create the mesh, prepare the layers with the input information, and run HydroBID Flood.

2.1 Starting a new project

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'Hoh_QGIS_Metric_Units' folder. This zip file is downloaded separately from your installation materials.

Name	Date modified	Type	Size
hohdem2.tif	5/3/2024 11:39 AM	TIF File	1,166 KB
HohDTM_points_METRIC.txt	6/26/2018 12:17 PM	Text Document	357 KB
Projection EPSG 2855 meters.txt	9/4/2018 10:38 AM	Text Document	0 KB
QIN.DAT	11/24/2019 10:54 AM	DAT File	1 KB

Figure 2.1 – Files with data required for the example.

The first step is to start the QGIS software clicking the QGIS desktop icon 

. If this icon is not available, you can run the 'qgis-bin.exe' executable on the QGIS 'bin' subdirectory.

After loading, you will see a window similar to the one shown below:




Figure 2.2 – QGIS interface indicating window areas.

For pre-v10 or standalone HydroBID Flood installations, if you don't see the toolbar with the model icons as shown, activate the standalone plugin using the *Manage and Install Plugins...* command under the *Plugins* menu.




Figure 2.3 – Plugins window showing standalone HydroBID Flood activated (pre-v10/standalone).

For version 10 and later, use the unified Hydronia2DMS plugin. In *Manage and Install Plugins…*, find Hydronia2DMS in the *Installed* list and confirm that it is enabled. Hydronia2DMS provides the HydroBID Flood-flavored tools used throughout this tutorial.





Figure 2.4 – QGIS Plugins window showing Hydronia2DMS installed for version 10 and later.

2.2 Start a new project

1. To create a new HydroBID Flood project, click on the *New HydroBID Flood Project* button  in the toolbar. to start a new HydroBID Flood project. A dialog window appears where you select the layers that will be created, the Coordinate Reference System (CRS), and the directory path where the layers will be saved. This example will use the basic layers: *Domain Outline*, *Manning N*, and *BoundaryConditions*

2. Select *None* in the Layers drop down menu.


3. Select the *Projection* button. In the *Filter* textbox, type *2855* and select the *Coordinate Reference System* as shown:



Coordinate Reference System Selector dialog window.

4. Click OK.

5. Select EPSG:2855 that corresponds to the NAD83(HARN)/Washington North Coordinate Reference System (CRS):




Create New HydroBID Flood Project.

6. Click the  button to provide a path to store the project files in the *Project Directory* textbox. This will be the folder where the model will write all results and output files.

7. After clicking OK, the layer templates are created, and displayed on the *Layers Panel*

The model will use the unit system as that defined in the projection you selected. If the projection has coordinates in feet, units will be set to English. If the projection coordinates are in meters, units will be set to Metric/SI.



Layers created for the project.


8. On the QGIS *Project* menu, click *Save*, to save the project in the same directory that you previously selected in the *Create New Project* dialog above.

2.3 Load elevation data

In this tutorial we will use a raster file that contains the terrain and river bed bottom elevation data in ASCII grid format.

1. To load an ASCII grid file, click the *Add Raster Layer* button  .

2. In the dialog search for the tutorial folder and select the 'hohdem2.tif' file as shown:




Dialog to create a layer from a raster file.

3. While on the dialog, click *Add* and click *Close*.


4. Use the *Zoom to Layer* button  to center the image.

   Once the process is completed, the raster will be displayed on the screen, by default it is rendered in gray gradient as shown.




Digital elevation model in raster format.

Right-clicking on the label of the new raster layer and selecting *Properties* allows you to change the rendering style for a more informative palette such as *Hillshade* for instance.



Window to change the raster layer render style.

And now the raster layer is displayed with the new palette selected:




Digital elevation model with Hillshade render.

5. You should move the raster layer dragging it to the end of the list of layers to avoid that it would hide or interfere visually with the other layers.

2.4 Create the limits of the modeling area

We define the limits of the modeling area drawing a polygon on the *Domain Outline* layer. To create it do as follows:

1. Click the *Domain Outline* layer to activate it and then click *Toggle Editing* (pencil) in the toolbar




2. This activates the rest of the editing buttons. Now click the *Add Feature* tool which is the bean-looking polygon  .

   Proceed to delineate the outline of the polygon by clicking the vertices with the left mouse button.

   Make sure that the polygon is contained within the limits of the raster layer since the program will not extrapolate elevations to areas that are outside of the available data on the raster layer.

3. To finalize and close the polygon, right-click on the map view area. A dialog window to input the cell size attribute of the newly created polygon will appear. The *CellSize* value for the reference size of the mesh cell is indicated. Enter a value of 20 m.



CellSize defined for the Domain Outline layer.

If you want to make any correction in the outline of the created polygon, use the *Node* Tool  .

4. Save the polygon by clicking the *Save* button  .

5. and click on *Toggle Editing* button to deactivate the layer Edit mode 

   The *Domain Outline* is now complete.



Figure 2.5 – Domain Outline layer.

2.5 Generating the triangular-cell mesh

Now that the *Domain Outline* layer has been created, proceed to create the mesh by clicking on the *Generate Trimesh* button
The following figure shows the generated mesh. You will also see in the Layers panel the new layer: *Trimesh*




Figure 2.6 – Resulting mesh.

You can see the mesh generation statistics, and other messages produced by the mesh generation program while creating the mesh in the Log messages panel. This window is accessed from the *View* menu, then by clicking *Panels*.

Log Messages Panel

General | Plugins | Processing | Python warning | Gmsh

```
2018-09-04T11:14:31 0    Info    : Meshing curve 105 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 106 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 107 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 108 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 109 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 110 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 111 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 112 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 113 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 114 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 115 (Line)
2018-09-04T11:14:31 0    Info    : Meshing curve 116 (Line)
2018-09-04T11:14:31 0    Info    : Done meshing 1D (0.015625 s)
2018-09-04T11:14:31 0    Info    : Meshing 2D...
2018-09-04T11:14:31 0    Info    : Meshing surface 1 (Plane, Delaunay)
2018-09-04T11:14:31 0    Info    : Done meshing 2D (0.046875 s)
2018-09-04T11:14:31 0    Info    : 1186 vertices 2486 elements
2018-09-04T11:14:31 0    Info    : Writing 'C:\Users\Hydronia Dell\Documents\RiverFlow2D_QGIS\ExampleProjects\Hoh_QGIS\TriMesh.msh'...
2018-09-04T11:14:31 0    Info    : Done writing 'C:\Users\Hydronia Dell\Documents\RiverFlow2D_QGIS\ExampleProjects\Hoh_QGIS\TriMesh.msh'
2018-09-04T11:14:31 0    Info    : Stopped on Tue Sep 04 11:14:31 2018
2018-09-04T11:14:31 0    Gmsh has been executed correctly
```


Figure 2.7 – Message panel of the registry with GMSH messages.

2.6 Setting up the boundary conditions

Inflow boundary conditions:

1. Select the *BoundaryConditions* layer in the Layers panel.

2. Click the *Toggle Editing* button  to add the polygons that will indicate the open boundary segments where inflow and outflow conditions are imposed. Draw a polygon at the upper end of the mesh as indicated in the figure:




Polygon that covers the nodes defining the Inflow boundary condition segment.

3. To finish the polygon, right-click on desired location. A window to enter the attributes of the newly created polygon is displayed.


4. In the *Boundary Cond. ID* enter the desired name or leave the default.

5. From *Type of Open Boundary* list, select *2. Discharge vs. Time*

6. Click *Import BC File* button, and search for the 'QIN.DAT' hydrograph file as shown below:



Inflow boundary condition parameters.




Hydrograph loaded from the 'QIN.DAT' file.

7. Click *OK* to close the dialog and then click *Save*  .


Outflow boundary conditions:

1. Draw the polygon defining the outflow boundary condition at the downstream end of the channel as shown.



Polygon that defines the outflow boundary condition segment.

2. Right click to close the polygon. A dialog window will appear to enter the parameters. Select the condition type *Uniform flow conditions* and enter the channel slope. Slope is entered in *So* as shown:




Parameters for the uniform flow outflow open boundary condition.

3. Save the changes made to the layer by clicking the *Save* button  .

4. Deactivate editing mode by clicking on the *Toggle Editing* button  .

   The figure below shows how the *BoundaryConditions* layer should look:




Polygons that define the inflow and outflow boundary conditions.

2.7 Assigning Manning's

To assign Manning's n values, we enter polygons with given n's. There can be as many polygons as those required to reproduce the spatial variability of this parameter. In this example, a single polygon will be drawn for the entire area.


1. Select the *Manning N* layer and click the *Toggle Editing* button

2. Draw a polygon that covers the entire domain. The polygon may extend beyond the mesh area as shown:



Capa Manning N.

3. Close the polygon by right-clicking on the end vertex and enter a Manning's n equal to 0.035:



Diálogo para ingresar ManningN.

4. Click *Save*  , and then click the *Toggle Editing* button  to deactivate editing mode.


Save the QGIS project using the *Save* command in the *Project* menu. Name the project file 'Hoh.qgs'.

2.8 Exporting the files

Once the layers with the input data to the model have been created, we need to export data files required to run HydroBID Flood.

1. In the HydroBID Flood plugin toolbar, click the *Export files for HydroBID Flood* button and select *Export HydroBID Flood …*
2. In the export dialog window indicate the *Scenario Name* and the raster layer of the Digital Elevation Model (DEM).


   The Scenario name is also the name that will be given to all of the exported files, these names should never be changed manually.
3. Click *OK*.



Export HydroBID Flood dialog.


A message at the top of the Map area shows the progress of the Export process.

In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.




Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.

Once the model files have been created, the Hydronia Data Input Program will appear automatically with the main control data file loaded, in this case: ‘Hoh.DAT’.



QGIS DIP Control Data panel for the Hoh tutorial.

The following Classic DIP panel is retained as a legacy values reference:




Legacy Classic DIP Hydronia Data Input Program window.

4. Click the *Run HydroBID Flood* button to run the model.

5. A Dialog box will ask if you want to save changs, no changes were made so select [No].

   An image similar to the one shown below should appear:



Window displayed while the model runs.

Take some time to explore the information included in this window.

This concludes the *Creating your first HydroBID Flood application* tutorial.

3 | Multiple Scenario Project Tool

When establishing a mathematical model of a system, it is very common to perform a variety of runs with different values of the most significant parameters to see their effects. In some cases, it is also useful to have the model run the scenario without a project and within a project. In previous versions of the plugin this had to be done in separate QGIS projects, which involved making copies of the project folders and data, which can bring problems with data handling and access. This new version of the HydroBID Flood plugin for QGIS allows the management of multiple scenarios within the same project. In this way variants of the same model can be created as subprojects, thus bringing with it the advantage of having all the variants organized in the same project which facilitates access and management of information. The following describes the new features of the QGIS interface for HydroBID Flood that allow the handling of multiple scenarios.

3.1 New interface elements for managing multi-scenario projects in HydroBID Flood

This section provides a description of the new elements in the QGIS user interface for handling HydroBID Flood multi-scenario projects. The HydroBID Flood toolbar now features three new items:

- A drop-down list that shows the user the list of scenarios contained in the project.
- An option to generate new scenarios in the *New HydroBID Flood Project* button.
- An option in the HydroBID Flood tools menu that allows you to import an existing HydroBID Flood project into the multi-scenario mode.

The figures below show the three new elements.




Figure 3.1 – Drop-down list for displaying and selecting project scenarios




Figure 3.2 – Tool to create a new scenario within the project




Figure 3.3 – Tool to convert existing project to multi-scenario

3.2 Creating a new HydroBID Flood multiple-scenario project using QGIS

- To create a new project into a multi-scenario project, access the first button on the toolbar and select the *New HydroBID Flood Project* menu option as shown in the figure below:




Figure 3.4 – Menu to create a new project

The dialog window presents a field for the name of the initial scenario (highlighted in a red box in the figure below), by default this field is labeled *base*. The drop-down list for displaying scenario names is limited in length, we recommend that you assign short names to scenarios for ease of viewing and to assign names without spaces.





Figure 3.5 – Dialog window to create a new HBF project

When creating a multi-scenario project, within the folder selected for the project a subfolder is created with the name given to the initial scenario, (in this example the folder name *base*)and within that sub-folder another subfolder is created with the name *shape* where QGIS creates the templates of the layers used by the model for that scenario. Each other scenario will have its own *shape* subfolder that contain the layers for that particular scenario.

3.3 Create a new scenario

Once we have a project created with the new Multi-scenario tool, we can start to create additional scenarios by following the steps in this section. *Please make sure to have either created a new project with the tool or have already converted an existing project before doing the following.*

- To create a new scenario, access the first button on the toolbar and select the *New Scenario* menu option as shown in the figure below:



Menu for creating a new scenario in an HBF project

- A window will be presented, input the scenario name keeping in mind to use short names without spaces.




Window to create a new scenario.

The new scenario is based on the layers with the input data of the current scenario. The plugin will proceed to create a subfolder with the name of the new scenario within the project folder. In this folder the files corresponding to the layers of the HydroBID Flood project will be copied with the input geospatial information it requires. Please note that the model layers will not copy post-processing products such as maps or animations. The plugin then updates the paths of the sources of the layers to the files in the new folder and finally the drop-down list in the HydroBID Flood toolbar is updated with the name of the new scenario.


3.4 Switching scenarios

- To switch between the different scenarios that you have in a project, simply display the scenario list located in the HydroBID Flood toolbar and select the desired scenario as shown in the following figure:



Switching scenarios

- Then a Dialog window will ask for confirmation to switch scenarios, as shown in the figure:



Confirmation window for switching the scenario.

When you switch scenarios, the state of the layers in the current scenario is automatically saved.

3.5 Deleting scenarios

To safely delete scenarios, the tool also contains a menu option to delete them when needed:

- Use the button below the New HydroBID Flood Project dropdown, and select Delete Scenario:





Figure 3.6 – Menu button to delete a scenario.

**IMPORTANT* Please note that deleting a scenario folder manually from the project directory will cause the entire project to be unusable. This tool must be used in order to avoid this.*

3.6 Import an HydroBID Flood project into Multi-scenario mode

The HydroBID Flood Multi Scenario tool has a feature that allows you to import an existing project(mono-scenario) and convert it to a multi-scenario project.

- Open this tool in the options menu of the HBF Tools button as shown in the figure below:



Menu to import a project to multi-scenario mode

- When you start the import tool a window is displayed as illustrated in the figure below, you must specify the project file. DAT to import.



Import tool window

- Once you click [OK], a subfolder with the name of the file is created inside the folder where the original project is located.
- All files and sub directories in that main project folder are copied, and the metadata of the project *QGZ* is updated with the new location of the layers.
- Finally the drop-down list on the HydroBID Flood toolbar is updated with the name of the new scenario.

The files of the original project are kept in the project folder, it is at the discretion of the user delete it if you think it necessary, the only one that is required then is the QGIS project file (.qgz) This concludes the tutorial on using the Multiple Scenario Project tool within the QGIS HydroBID Flood toolbar.

4 | Simulating levees using weirs

This tutorial illustrates how to incorporate a levee to an existing HydroBID Flood project using the Weirs Component in the QGIS interface. The problem consists in modeling a lateral weir along the right margin of a river, as can be seen in the following figure:



Figure 4.1 – The weir polyline representing the levee is shown in red.

The procedure to incorporate the weir in a HydroBID Flood simulation involves the following steps:


1. Open an existing HydroBID Flood project.
2. Add the *Weirs* layer.
3. Draw the weir polylines.
4. Input the weir parameters or attributes.
5. Export the files to HydroBID Flood.
6. Run the HydroBID Flood model.
7. Review the output files.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'WeirTutorial' folder. This zip file is downloaded separately from your installation materials.

4.1 Open an existing project

1. Open QGIS.
2. On the *Project* menu click *Open…* and browse to select the existing project: .


   This project contains the following layers: Domain Outline, Digital Elevation Model (DEM) of the river bed in raster format, aerial photography, polygon with the Manning coefficient and the polygons with the boundary conditions where the flow entrance is in the upper left corner and exit in the lower left corner. The boundary conditions are a hydrograph with a peak discharge of 220,000 ft^3/s, and outflow condition is set to *uniform flow*. When you open the project you will have a project image loaded in QGIS as shown in Figure 4.2:



4.2 Create a Weirs layer and the weir polyline

The weir location can be drawn on the *Weirs* layer or it can be imported from an existing file. In this tutorial, the polyline that indicates the location of the weir will be imported from a text file. The structure of the file should be as follows:

- The first line must indicate the number n of nodes that contains the polyline.
- The *n* successive lines will contain three columns with the X, Y coordinates.
- The elevation of the weir crest separated by space as shown in Figure 4.3:




Adding the *Weirs* layer involves the following steps:

1. Create *Weirs* layer: for this click on the *New Template Layer* button in the HydroBID Flood toolbar



2. Activate the checkbox Weirs, as shown in the Figure below:



Plugin to add a new template layer.

3. Edit the *Weirs* layer: In the layer panel, select the *Weirs* layer and in the digitization toolbar click on the *Toggle Editing* button



A pencil icon will appear in the *Weirs* layer indicating that the layer is in edit mode:



4. Draw the line representing the weir: Using the *Add Feature* tool from the digitization toolbar




Draw a line anywhere in the map area (just mark two vertices or nodes. This line will then be replaced by the coordinates of the file to be imported).

5. Right-click to finish the layout and a dialog window will appear to input the weir parameters.

6. Input the weir parameters: The window to input the weir attributes contains two tabs. In the first one there are the fields of the general parameters, within which has:


   - Weir Name (ID): Weir1
   - Weir discharge coefficient: 3.2
   - Weir crest elevation for all the weir: since a file will be imported this field will be left empty.
   - Size Element: 150
   - Import Geometry File: Click the [...] button and point to the file *LeveeRB_Breakline.txt* which is found in the tutorials folder.

   The weir parameters window should look like the image shown below:



   Window to input Weir parameters.

   In the second tab 'Weir crest elevation for vertex' the data contained in the file *LeveeRB_Breakline.txt* is displayed, as shown in the following Figure:



   Window for weir geometry data.

7. Then click on the [OK] button.


8. Save the changes in the layer using the *Save* button of the digitization toolbar



9. Disable the editing mode of the layer with the *Toggle Editing* button



and we will have on screen an image similar to the one shown below where you can see the layout of the weir:




Weir alignment loaded from the file.

4.3 Generate the mesh

The mesh is generated with the *Generate TriMesh* plugin.



result should look similar to the image on Figure 4.8.



4.4 Exporting files to HydroBID Flood


Now that you have generated the mesh and you have the other layers ready with the necessary data, you should export the files in the format required by HydroBID Flood.

1. Click the *Export to HydroBID Flood* button.




2. When running the plugin a window is displayed, here we must select the raster layer that contains the Digital Elevation Model (DEM) and the name of the project to be exported.


   Once the plugin is executed, a window will be shown (Figure 4.9), as it should be for our example.



3. After inputting the data, click on the OK button and the export process will begin. Once it is finished, Hydronia Data Input Program will be loaded as shown in Figure 4.10



In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.





Figure 4.2 – QGIS DIP Control Data panel for the Weirs tutorial.


4.5 Running the model

Make sure that the Weirs Component appears selected in the Control Data panel.

1. In the list of components, select ‘Weirs’ and the panel of the Weirs component will appear. In this window the contents of the ‘.WEIRS’ file content as prepared by HydroBID Flood will be displayed (Figure 4.11).




The following Classic DIP panel is retained as a legacy values reference:



2. Leave all other parameters at their default values.

3. Click on the *Run HydroBID Flood* button in the lower section of Hydronia Data Input Program. A window will appear indicating that the model began to run. The window also informs the simulation time, the volume conservation error, the total input and output discharge and other parameters as the execution progresses (Figure 4.12).



4.6 Review the output files

HydroBID Flood creates an output file with the name of the project and extension '.WEIRI' for metric units and '.WEIRE' for English units. The files report results for each weir and for each output interval. Output includes the following information:

- EDGE: The segments into which the weir is divided and is given by the length of the cells in contact with the weir.

- N1 y N2: The numbers that identify the cells that share the EDGE segment in the weir.
- WSE1 y WSE2: The elevations of the water surface in the cells indicated by N1 and N2.
- D1 y D2: The depths of the flow in the cells indicated by N1 and N2.
- Distance: The length of the EDGE segment.
- Q: The discharge that passes through the EDGE segment.

The '.WEIRE' file contains the following:

```
================================================================================
================================================================================
                          RiverFlow2D
                          Build Jan 11 2023
================================================================================
             TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
                        (R) TRADEMARK 2009-2022 Hydronia, LLC.
                                    ALL RIGHTS RESERVED
                                    RUN DATE: 07/Mar/2023
================================================================================

 WEIR RESULTS IN ENGLISH UNITS

 TIME: 0000 days,00 hours,00 min.,36 secs.
 WEIR NO.:   1 WEIR ID: WEIR_1
 EDGE      N1        N2       WSE1      WSE2       D1        D2     Distance     Q
                              (ft)      (ft)      (ft)      (ft)      (ft)     (ft3/s)
   1      3527      3526    126.54    125.57      0.00      0.00    150.00      0.00
   2      1924       826    126.21    121.34      0.00      0.00    150.00      0.00
   3      1602      2300    122.37    125.74      0.00      0.00    150.00      0.00
   4      1550      1920    124.08    124.55      0.00      0.00    150.00      0.00
   5      2082      2022    122.46    123.21      0.00      0.00    150.00      0.00
   6      1408       390    122.98    123.34      0.00      0.00    150.00      0.00
   7       218      1467    122.39    121.30      0.00      0.00    112.08      0.00
   8      1852       233    120.44    121.03      0.00      0.00    112.08      0.00
   9      1612      1701    118.89    119.54      0.00      0.00    150.00      0.00
  10      2673       612    116.88    121.21      0.00      0.00    150.00      0.00
  11      2655       663    116.30    119.45      0.00      0.00    150.00      0.00
  12       497      1205    118.31    116.70      0.00      0.00    150.00      0.00
  ...
  35       124      3528    126.02    125.67      0.00      0.00    150.00      0.00
  36      2942      1828    125.44    125.13      0.00      0.00     77.15      0.00
  37      2713      3058    126.08    125.39      0.00      0.00     77.15      0.00
  38      3529       146    125.90    124.67      0.00      0.00    150.00      0.00
  39      1657      1291    124.16    123.69      0.00      0.00    150.00      0.00
  40        24       703    129.60    122.82      0.00      0.00    150.00      0.00
  41      2409       513    122.99    122.74      0.00      0.00    150.00      0.00
  42       576      2019    123.54    125.30      0.00      0.00    150.00      0.00
  43      1792      1336    123.59    124.66      0.00      0.00    135.26      0.00
  44       366        38    123.66    122.73      0.00      0.00    135.26      0.00
  45      2512      1213    124.92    122.49      0.00      0.00    150.00      0.00
  46        79       770    118.60    123.20      0.00      0.00    150.00      0.00
  47      2377      1952    122.27    120.39      0.00      0.00    150.00      0.00
  48      1032      2403    121.93    120.42      0.00      0.00    150.00      0.00
  49      2701      2392    124.20    121.53      0.00      0.00    150.00      0.00
  50       182       636    132.78    131.33      0.00      0.00    150.00      0.00
  51       714       328    129.90    130.42      0.00      0.00    150.00      0.00
  52      2389      1618    129.03    125.76      0.00      0.00     86.95      0.00
  53      2884      2666    130.49    125.35      0.00      0.00     86.95      0.00
Total discharge over weir Q =      0.000 m3/s
```

Figure 4.3 – Extract of the output file of the Weir1.

This concludes the *Simulating Levees using Weirs* Tutorial.

5 | Simulating bridges

This tutorial illustrates how to incorporate a bridge into an existing HydroBID Flood project using the Bridge Component through the QGIS interface. The procedure involves the following steps:

1. Create the bridge geometry data.
2. Open an existing HydroBID Flood project.
3. Enter the bridge polyline.
4. Enter the bridge data.
5. Generate the mesh.
6. Export the files of HydroBID Flood.
7. Running the model.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'BridgesTutorial' folder. This zip file is downloaded separately from your installation materials.

5.1 Create a bridge geometry file

Integrating bridges in HydroBID Flood requires preparing the bridge cross section geometry data prior to running the model. With the QGIS interface you have the option of creating a simplified bridge geometry from the terrain profile obtained from the digital elevation model, and then you can use the Bridges panel in the Hydronia Data Input Program to perform the adjustments necessary to the geometry generated by QGIS. This option is useful when the bridge is located on a natural section of the river, and the geometry of the bridge is simple (Figure 5.1a). However, other cases may involve more complex bridge geometries (Figure 5.1b), that require a more detailed preparation of the bridge geometry file.





Figure 5.2 shows the front view of the bridge that you want to incorporate into the model for this tutorial. The data is also in the file 'BRIDGEGEOMETRY.DAT' contained in the directory of this tutorial.




It represents the cross section of a bridge with only one central pier, although this is just for the purpose of illustrating the Bridges component in this tutorial since the actual bridge in this location has about 12 sets of piers. This geometry is represented in the HydroBID Flood model using the bridge geometry file shown below, where the header row is presented only to describe the parameters, and they should not be included in the actual data file:

NP	22	X (Station)	BedElev	ZLower	LowChord	DeckElev
		0.000	142.000	142.000	142.000	142.000
		96.684	125.724	125.724	138.000	142.000
		193.367	123.034	123.034	138.000	142.000
		290.052	119.860	119.860	138.000	142.000
		386.736	110.366	110.366	138.000	142.000
		483.420	109.004	109.004	138.000	142.000
		580.103	107.578	107.578	138.000	142.000
		676.787	106.350	106.350	138.000	142.000
		750.000	106.298	106.298	138.000	142.000
		750.000	106.298	106.298	106.298	142.000
		751.000	106.298	106.298	106.298	142.000
		751.000	106.298	106.298	138.000	142.000
		870.155	105.182	105.182	138.000	142.000
		966.839	106.772	106.772	138.000	142.000
		1063.524	107.302	107.302	138.000	142.000
		1160.207	116.470	116.470	138.000	142.000
		1256.891	116.018	116.018	138.000	142.000
		1353.575	116.094	116.094	138.000	142.000
		1450.259	119.608	119.608	138.000	142.000
		1546.943	120.924	120.924	138.000	142.000
		1643.627	124.736	124.736	138.000	142.000
		1740.311	142.000	142.000	142.000	142.000

Figure 5.1 – Data of the bridge geometry.

You may use the *Bridges* panel in Hydronia Data Input Program to create to some extent, or edit a bridge geometry file (see Figure 5.4). The program lets you enter data in tabular form and view a graph of the bridge geometry. You may also manipulate the graphical lines, which will make that the tabular data be modified.




An alternative way to create the bridge geometry file is to use a spreadsheet. In the folder for this tutorial there is a MS-Excel sheet ('BridgesGeometryPlot.xlsx') that allows editing and plotting bridge geometry files.

5.2 Open an existing project

1. On the *Project* menu click *Open…* to load the existing project: .

   This project contains the layers of the domain contour, the Digital Elevation Model DEM of the river bed in raster format, the polygons with the Manning's n for the different land coverages, an aerial image, and the boundary conditions. Inflow is located in the upper right segment, and outflow in the lower left. The boundary conditions are a hydrograph with a peak discharge of 220,000 ft^3/s (cfs), and outflow condition is set to uniform flow. When you open the project you will have an image of the project loaded in QGIS as shown in Figure 5.5.




5.3 Enter the bridge polyline in the *Bridges* layer

This step ensures that the mesh will conform to the bridge alignment, so that there will be nodes generated along the bridge. In this case we will enter the bridge as a straight line approximately 1740 feet long as follows:

1. Create a new *Bridges* layer: for this, go to the HydroBID Flood toolbar and left click on the *New Template Layer* button



   In the plugin window we activate the Bridges checkBox, as shown in the Figure below.



HydroBID Flood dialog to add new layer.

2. Edit the *Bridges* layer: In the layers panel we select the *Bridges* layer then in the digitization toolbar we left click on the *Toggle Editing* button  .

   A pencil icon will appear in the *Bridges* layer that tells us that the layer is in edit mode:



3. Draw the line representing the bridge: (if necessary, turn off the DEM layer so that it does not interfere with the identification of the bridge site in the aerial photograph).

4. Using the *Add Feature* button of the digitization toolbar  , draw the line indicating the location of the bridge. In the case shown, to demarcate the line that indicates the location of the bridge. It is only necessary to indicate two vertices (initial and final), then right-click to finish the drawing.

   We will have an image similar to the one shown in the following figure:




Bridge drawing.

5. Enter the bridge data: After the bridge layout is finished, the window to input the attributes of the bridge is immediately displayed, these are:

   - Bridge Name (ID): Bridge1
   - Size Element: 150 feet
   - Click on the [Import Geometry Bridge File] button to select the Bridge file: BRIDGEGEOMETRY.dat in the Data folder of this tutorial.
   - Elevation of the lower bridge deck (LOWCHORD): 138
   - Elevation of the bridge deck (DECKELEV): 142

   The figure below shows the attributes window of the *Bridges* layer:



Attribute dialog window of the Bridges layer.

6. After entering the values, click on the [Check Fields] button, then click the [OK] button.

7. Save the changes in the layer using the *save* button of the digitization toolbar:




and disable the editing mode of the layer with the *Toggle Editing*



5.4 Generate the mesh

The mesh is generated using the *Generate TriMesh* icon:





Check that the resulting mesh is perfectly aligned with the bridge as shown in Figure 5.9.

5.5 Exporting files to HydroBID Flood


Now that you have generated the mesh, and you have the other layers with the necessary data ready, you should export the files in the format required by HydroBID Flood.

1. Click on *Export HydroBID Flood* button:



In the export files dialog we need to make sure that the appropriate raster layer corresponding to the Digital Elevation Model (DEM) is selected. The *Project Name* will already be set.


The dialog should look as follows:



Export HydroBID Flood tool.

2. Click on the [OK] button and the export process will begin.

   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.




Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


Once finished, the *Data Input Program* will be loaded with the '.DAT' file of the specific example.

5.6 Running the Model


After exporting the files, the HydroBID Flood program is loaded with the project file of the ‘bridge.DAT’ example, and the *Control Data* panel is shown (Figure 5.11).



The following Classic DIP panel is retained as a legacy values reference:




Select the Bridges panel to review the contents of the bridge geometry file (Figure 5.12). Note how the bridge profile was discretized every 150 feet according to the element size imposed to the bridge




line.

The following Classic DIP panel is retained as a legacy values reference:



Leave all other parameters at their default values.

To run the model, click on the Run HydroBID Flood button in the lower section of Hydronia Data Input Program. A window will appear indicating that the model run started. The window also reports the simulation time, the volume conservation error, the total input and output discharge, and other pa-



rameters as the execution progresses (Figure 5.13).

Once this process completes, check the outputs in the scenario folder to review the ‘BridgeTutorial.bridgeh’ file:

```
================================================================================
================================================================================
                          RiverFlow2D
                          Build Jan 11 2023
================================================================================
             TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
                       (R) TRADEMARK 2009-2022 Hydronia, LLC.
                                   ALL RIGHTS RESERVED
                                   RUN DATE: 07/Mar/2023
================================================================================

 Hydrograph and levels evolution for bridges in cfs and ft, respectively, time in hours

  Time        BRIDGE_1

0.000000       0.000
0.001989       0.000
0.010268       0.000
0.020462       0.000
0.030420       0.000
0.040024       0.000
0.050091       0.000
0.060276       0.000
0.070284       0.000
0.080190       0.000
0.090034       0.000
0.100000       0.000
0.110101       0.000
0.120263    5577.106
0.130107   27184.073
0.140286   41709.887
0.150139   55059.389
...
1.920158  218207.372
1.930236  218237.844
1.940075  218251.257
1.950155  218203.221
1.960232  218241.509
1.970072  218260.448
1.980150  218271.445
1.990228  218251.071
2.000000  218237.858
```

Figure 5.2 – Bridge hydrograph file '.bridgeh'.

This concludes the *Simulating bridges* tutorial.

6 | Simulating culverts

This tutorial shows how to incorporate culverts in an existing HydroBID Flood project using the QGIS interface. The problem consists of a natural channel crossed by a road embankment. A culvert structure is to be used to connect the upstream and downstream parts of the channel divided by the embankment as shown in the following figure:




Figure 6.1 – Culvert scheme.

The water enters from upstream with a constant discharge of 1000 cfs, and outflows downstream along the indicated section. The area is initially dry. The culvert has a circular cross section, and other characteristics as summarized in the following Table (CulvertA). CulvertB data is provided in case that you wanted to extend the tutorial adding a second culvert to the project.

Parameter	Description	Culvert A	Culvert B Nb	Number of identical barrels	1	1
Ke	Entrance Loss Coefficients	0.5	0.7			
n	Manning's n Coefficient	0.014	0.015			
Kp	Inlet Control Coefficient	0.3	0.4			
M	Inlet Control Coefficient	2	2			
Cp	Inlet Control Coefficient	1.28	1.1			
Y	Inlet Control Coefficient	0.67	0.69			
m	Inlet Control Coefficient	-0.5	-0.5			
Dc	Diameter (feet)	3	2			
-	Inlet Inverted elevation	-9999	-9999			
-	Outlet Inverted elevation	-9999	-9999			

The procedure to integrate this culvert into a HydroBID Flood simulation involves the following steps:

1. Open an existing HydroBID Flood project.
2. Add a Culvert component layer.
3. Draw the line of culvert alignment.
4. Input the data or attributes for the culvert.
5. Export the files to the HydroBID Flood program.
6. Running the model.
7. Review culvert output files.


The files required to follow this tutorial can be extracted from the ‘ExampleProjects’ zip file under the ‘CulvertTutorial’ folder. This zip file is downloaded separately from your installation materials.

6.1 Open an existing project

1. Open QGIS.

2. On the *Project* menu click *Open…* and browse to the existing project: .

This project contains the following layers: Domain Outline, Digital Elevation Model (DEM) in raster format, polygon with the Manning’s n coefficient, and the boundary condition polygons. The inflow is located in the upper left, and the outflow in the lower left. The boundary conditions corresponds to a constant discharge of 1000 ft^3/s, and outflow conditions is set to free. Figure 6.2 shows the opened project.




6.2 Create Culverts layer and draw the culvert

1. To create the *Culverts* layer, in the HydroBID Flood toolbar click on the *New Template Layer* icon



2. In the window select the Culverts checkBox, as shown:




Plugin to add a New Template Layer.

3. Edit the *Culverts* layer: In the layers panel select the *Culverts* layer and in the digitization toolbar click on the *Toggle Editing* button



A pencil icon will appear in the *Culverts* layer indicating that the layer is in edit mode:




4. Draw the line representing the culvert alignment: Using the tool *Add Feature* from the digitization toolbar



draw the line that represents the culvert. It is only necessary to indicate two vertices.


5. Right-click to finish drawing. You should get an image similar to the one shown in the following Figure:



Culvert alignment.

6. Enter the culvert data: After the culvert drawing is finished, the window to input the culvert attributes immediately appears. The dialog window has 2 tabs, in the General tab you enter the basic data for circular and box culverts:

   - Culvert Name (ID): CULVERT_1,
   - Type of culvert: Type 3 (Circular culvert)
   - The rest of the parameters are coefficients that needed to compute the culvert discharge. To help with the introduction of these parameters, the window presents a list with default values for different types of culverts. If one of the values of the list parameters is not appropriate, you can choose the option where the value is defined by the user (user defined). The window of the culvert parameters should be similar to the one shown in the Figure below:



Window to input Culvert parameters.

7. After inputting the values, click on the *OK* button.

8. Save the changes in the layer using the *Save* button of the digitization toolbar



9. Disable the editing mode of the layer with the *Toggle Editing* button




6.3 Generate the mesh

The mesh is generated with the *Generate Trimesh* tool



the results obtained as shown in Figure 6.6.



6.4 Exporting files to HydroBID Flood


Now that you have generated the mesh and you have the other layers ready with the necessary data, you should export the files in the format required by HydroBID Flood.

1. Click the *Export HydroBID Flood* button



2. The raster layer that contains the Digital Elevation Model (DEM) and the name of the scenario should already be set.

A window will appear as shown in (Figure 6.7).



Once done reviewing, click on the [OK] button and the export process will begin. Once finished processing, the HydroBID Flood program will be loaded with the 'CulvertTutorial.DAT' file.
In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.





Figure 6.2 – Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


6.5 Running the model

After exporting the files, the HydroBID Flood program is loaded with the project file from the 'Culvert-



Tutorial.DAT' example and shows the *Control Data* panel to it as illustrated in Figure 6.8.

The following Classic DIP panel is retained as a legacy values reference:



Note that the Culverts Component appears selected. On the left side of the *Control Data* panel, in the list of components select *Culverts* to activate the *Culverts* panel. The contents of the culvert file prepared by QGIS will be displayed (Figure 4.10).




Figure 6.3 – QGIS DIP Culverts component panel.

The following Classic DIP panel is retained as a legacy values reference:





Figure 6.4 – Legacy Classic DIP Culverts component data panel.

Leave all other parameters at their default values.

To run the model, click on the *Run HydroBID Flood* button in the lower section of Hydronia Data Input Program. A window will appear indicating that the model began to run. The window also reports the simulation time, volume conservation error, total input and output discharge, and other parameters



as the execution progresses (Figure 6.10).

6.6 Review culvert output file

For each culvert, HydroBID Flood creates an output file called: ‘CULVERT_culvertID.out’, where ‘culvertID’ is the name (ID) entered when we created the culverts. Output includes the series of discharge versus time through the culvert and the elevations of the water surface at the inflow and outflow locations. For this tutorial, you will find a file called ‘CULVERT_CULVERT_1.out’, whose content is shown in the following figure:

```
================================================================================
================================================================================
                           RiverFlow2D
                           Build Jan 11 2023
================================================================================
             TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
                        (R) TRADEMARK 2009-2022 Hydronia, LLC.
                                    ALL RIGHTS RESERVED
                                    RUN DATE: 08/Mar/2023
================================================================================


================================================================================
Results for Culvert no.:            1 Culvert ID: CULVERT_1
================================================================================
 Time       Qc       WSEL1     WSEL2
 hrs.         ft3/s     ft.       ft.
0.01060   0.000   152.786    154.958
0.02021   0.000   152.786    154.958
0.03074   0.000   152.786    154.958
0.04055   0.000   152.786    154.958
0.05035   0.000   152.786    154.958
0.06039   0.000   152.786    154.958
0.07043   0.000   152.786    154.958
0.08015   0.000   152.786    154.958
0.09003   0.000   152.786    154.958
0.10000   0.000   152.786    154.958
0.11024   0.000   152.786    154.958
0.12035   0.000   152.786    154.958
0.13015   0.000   152.786    154.958
...
1.88018   91.611   166.127    155.720
1.89001   91.726   166.154    155.721
1.90000   91.848   166.183    155.723
1.91009   91.980   166.214    155.724
1.92017   92.115   166.246    155.725
1.93025   92.236   166.275    155.726
1.94004   92.436   166.301    155.706
1.95011   92.426   166.323    155.731
1.96016   92.466   166.344    155.743
1.97021   92.560   166.366    155.743
1.98025   92.662   166.390    155.743
1.99000   92.770   166.416    155.745
2.00000   92.901   166.448    155.746
```

Figure 6.5 – Culvert1 output file.

This concludes the *Simulating culverts* tutorial.

7 | Simulating dam breaches

This tutorial illustrates how to incorporate dam breach simulation into an existing HydroBID Flood project using the QGIS interface. The exercise consists of modeling a dam break flood. The dam is approximately 1575 feet long, the breach center is 550 feet from the right margin of the dam, the opening of the breach has the final dimensions shown in the following Figure, a top width of 160 feet,



and at the bottom width of 100 feet, the final breach height is 30 feet.
For this exercise, a file with the time evolution of the breaching dimensions is required, this file can be prepared before setting the model or it can be created when entering the input the parameters. The procedure to model the dam break involves the following steps:


1. Open an existing HydroBID Flood project.
2. Create a *DamBreach* layer and to draw a line that represent the transverse axis of the dam.
3. Generate the mesh.
4. Run the model.
5. Review the output files.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'DamBreachTutorial' folder. This zip file is downloaded separately from your installation materials.

7.1 Open an existing project

1. Open QGIS
2. On the *Project* menu click *Open…* and browse to the existing project: .

This project contains the *Domain Outline* layer, the digital elevation model DEM of in raster format, outflow conditions are set to free outflow in the lower left, and an initial condition of water surface elevation behind the dam. Figure 7.2 shows the project in QGIS.




7.2 Create the DamBreach layer and draw the line that defines the dam

Creating the dam involves the following steps:

1. Create the template for the *DamBreach* layer: in the HydroBID Flood toolbar click on the *New Template Layer* button



2. In the dialog select *DamBreach*, as shown in the figure below:




Dialog to add a new layers.

3. Edit the *DamBreach* layer: In the layers panel, select the *DamBreach* layer.

4. In the digitization toolbar we click on the *Toggle Editting* button




A pencil icon will appear in the *DamBreach* layer, indicating that the layer is in edit mode:



5. Draw the line that defines the axis of the dam: Using the *Add Feature* tool of the digitization toolbar




6. Draw the line that defines the dam axis. Keep in mind that the breach centroid is measured from the first vertex of the dam line. In this example it occurs 550 feet from the left margin of the dam (Figure 7.1). The dam axis is drawn from the top of the channel (point v0) to the bottom (point v1) along one side of the polygon that defines the initial water surface elevation, as illustrated in the image below.



Dam axis.

7. Once finished drawing the dam axis, the window to input the parameters of the *DamBreach* appears.

8. Input the information as seen below in the figure and click the *Check Fields* button:



Dialog to input the dam breach parameters.

9. Click the *Temporal evolution* tab and click on the *Import Dam Breach File* button. Select the 'DAMBREACH_1.txt' file in the scenario folder. Click *OK* to close.


10. The temporal evolution of the 'DAMBREACH_1.TXT' file is shown in the *Temporal evolution* tab below:

General | Temporal evolution

Dam Breach File: DAMBREACH_1.txt | Import Dam Breach File

	Time(hr)	Width(ft)	Height(ft)
1	0	0	0
2	0.5	7	3
3	1.0	20	5
4	1.5	45	12
5	2.0	100	30
6	3	100	30
7			

Evolution of the breach of the dam.



Dam axis.

7.3 Generate the mesh

The mesh is generated using the *Generate TriMesh* tool







Figure 7.8 shows the resulting mesh of almost 11,000 cells

7.4 Exporting files to HydroBID Flood

1. Click on the *Export HydroBID Flood* button.



2. Select the raster layer that contains the Digital Elevation Model (DEM) and the name of the project.




Export dialog.

3. Once finished, click on the OK button and the export process will begin. Once it is finished, HydroBID Flood will be loaded with the 'base.DAT' file.

   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone


alternative, expand *More options*, select *Classic DIP*, and then click *OK*.




Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.

7.5 Running the model

After exporting the files, Hydronia Data Input Program is loaded with the project file of the 'base.DAT' example and shows the *Control Data* panel as illustrated in Figure 7.10.



The following Classic DIP panel is retained as a legacy values reference:



It can be seen that the *Dam Breach* component is selected as well as the initial condition that indicates that the initial elevation of the water surface of the '.FED' file will be read. Selecting from the list on the left panel the *Dam Breach* component will show the panel where you can see the parameters of the dam breach as shown in the figure below:




Figure 7.1 – QGIS DIP Dam Breach component panel.

The following Classic DIP panel is retained as a legacy values reference:




Figure 7.2 – Legacy Classic DIP Dam Breach component.


1. Before running the model, set the simulation time to 4 hours.

2. Leave all other parameters at their default values.

3. To run the model, click on the Run HydroBID Flood button in the lower section of Hydronia Data Input Program.

4. Save the changes with the same name as the ‘DamBreach.DAT’ file.

A window will appear indicating that the model has started running. The window that HydroBID Flood presents while running the model shows simulation time information, volume conservation error, the total input and output discharge as well as other parameters as execution progresses (Figure 7.12).


RiverFlow2D Plus
Simulation Status
L3 Msgs (20)
L2 Msgs (2)
L1 Msgs (11)
Nodes read 5668
Cells read 11077
Mesh loaded
Found 27 outlet boundary walls with label :
Outlet boundary conditions ready
Boundaries ready
Erosive/piping dambreach file read
RiverFlow2D setup loaded
Initial conditions assigned from .FED file
Dambreach ready
Simulation setup ready
77.40
Topography (ft)
207.06
0.00
Water Depth (ft)
24.42
Info
Info Activated
Kernel compilation: Feb 12 2024
The number of threads is set to 24
Simulation completed
Elapsed time (HH:MM:SS): 00:01:13
Simulation
t (D H:M:S)
Δt (s.)
Volume Error (%)
Q Inflow (ft³/s)
Q Outflow (ft³/s)
0000 04:00:00
0.229318
0.000000e+00
0.000000
9384.576429
Total Inflow
Total Outflow
Volume Error
Discharge (ft^3/s)
20000
15000
10000
5000
0
1E-10
6E-11
2E-11
-2E-11
-6E-11
-1E-10
Volume Error [%]
00:00:00
01:00:00
02:00:00
03:00:00
04:00:00
Time
Progress
Pause
Close

7.6 Review the output files

HydroBID Flood output the dam breach hydrograph in a file with extension '.dambreachh'. Figure 7.13 shows a section of that file for this exercise.

```
==========================================================================
==========================================================================
   RiverFlow2D
   Build Feb 12 2024
==========================================================================
   TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
   (T) TRADEMARK 2009-2022 Hydronia, LLC.
   ALL RIGHTS RESERVED
   RUN DATE: 02/Jul/2024
==========================================================================

   NOTES:
   [Q in cfs]
   [z_b in ft]
   [b in ft]
   [B in ft]
   [z_top in ft]
   [type (1=User-given, 2=Erosive breach, 3=Piping flow)]

            DAMBREACH_1
  Time          Q         z_b          b          B         z_top

 0.000       0.000     149.000       0.000       0.000     149.000
 0.000       0.000     149.000       0.001       0.001     149.000
 0.010       0.000     148.940       0.140       0.260     149.000
 0.020       0.000     148.880       0.281       0.521     149.000
 0.030       0.000     148.820       0.420       0.780     149.000
 0.040       0.000     148.760       0.560       1.041     149.000
 0.050       0.000     148.700       0.700       1.300     149.000
 0.060       0.000     148.640       0.840       1.560     149.000
 0.070       0.000     148.580       0.980       1.821     149.000
 0.080       0.000     148.520       1.121       2.081     149.000
 0.090       0.000     148.460       1.260       2.341     149.000
 0.100       0.000     148.400       1.400       2.600     149.000
 0.110       0.000     148.340       1.540       2.860     149.000
 0.120       0.000     148.280       1.681       3.121     149.000
 0.130       0.000     148.220       1.820       3.381     149.000
 0.140       0.000     148.160       1.960       3.640     149.000
 0.150       0.000     148.100       2.100       3.900     149.000
 0.160       0.000     148.040       2.241       4.161     149.000
 0.170       0.000     147.980       2.381       4.421     149.000
 0.180       0.000     147.920       2.520       4.681     149.000
 0.190       0.000     147.860       2.660       4.940     149.000
```

This concludes the *Simulating dam breaches* tutorial.

8 | Establishing initial water, mud, or tailings elevations

Sometimes it is practical to use a raster layer to establish the initial condition of the water surface elevation (Initial WSE). For instance, when modeling tailings dam breaks, it is often necessary to define the initial surface of the tailings behind the dam.

This tutorial illustrates how to use a raster file that contains the initial elevations of the fluid contained by a dam with the purpose of simulate a dam breach and determine the fluid runout after the dam collapses.

The procedure of modeling a dam-breach using an initial condition of fluid surface elevation involves the following steps:

1. Open an existing HydroBID Flood project.

2. Import a raster layer with the initial values of the water surface elevation (WSE).

3. Export the files to HydroBID Flood by setting the option to use the raster layer with the Initial WSE.

The files used in this tutorial can be found in the following directory:

Documents\Hydronia\HydroBIDFlood\ExampleProjects\initialWSE_RasterTutorial

8.1 Open an existing HydroBID Flood project

Start QGIS and in the *Project*, use the *Open...* command to load the existing project: 'Initial-WSE_RasterTutorial.qgs'. The project corresponds to a model of a dam breach with an initial elevation of the fluid surface that is not horizontal but varies in space.

When you open the project you will have an image of the project loaded in QGIS as shown in the Figure 8.1.





Figure 8.1 – Project screen loaded in QGIS.

8.2 Importing the Initial WSE raster layer

The procedure to import the Initial WSE raster layer to the project includes the following steps:

1. Open the ASCII grid file representing the initial condition elevations clicking on on the *Add Raster Layer* button  and selecting the 'InitialWSE_r.tif' file.
2. Confirm the CRS 2229 projection that will be used for this layer
3. If necessary, move the new layer under the group *MESH_SPATIAL_DATA*. You should have an image on the screen like the one shown below:




Initial WSE raster layer.

The image shows the *InitialWSE_r* raster layer in a grayscale gradient where there is a change in the WSE ranging from 135.0 to 135.4 ft.

The window above has the *Trimesh* layer disabled for clarity. Re-enable it for the export process in the next section.

8.3 Exporting files to HydroBID Flood

1. Export the files in the format required by the HydroBID Flood using the Export to HydroBID Flood plugin. When executing the plugin a window like the one shown in the Figure 8.3 is shown.



Plugin window to export the files to HydroBID Flood.


As shown in the figure, click the *Options* arrow to display the group of options that appear hidden by default.

2. Select the DEM raster in the *DEM (Single Raster)* drop down.

3. Check the box *Using Initial WSE Raster Layer*. Select the *InitialWSE_r* layer from the drop-down list.

4. Click OK button and the export process will begin.

   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.

From this point on, You can refer to the Dam Breach tutorial to continue with the modeling of the dam breach.

9 | Simulating bed load sediment transport with limited erosion bed areas

In the Sediment Transport model you can define areas with a maximum erosion depth. This is useful to represent pavements, rock outcrops or any surface that does not erode or that it has a known erodible layer of sediment above it. This tutorial illustrates how to perform a sediment transport simulation in which there is a non-erodible area using the QGIS interface. The procedure includes the following steps:


1. Open an existing HydroBID Flood project.
2. Create a 'MaximumErosionDepth' layer and the polygons that define the limited erosion areas.
3. Generate the mesh.
4. Running the model.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'MaxErosionDepth' folder. This zip file is downloaded separately from your installation materials.

9.1 Open an existing project

1. Open QGIS
2. In the main menu go to *Project* > *Open…* and browse to the existing tutorial folder.

This project contains the layers of the domain outline, of the digital elevation model DEM of the river bed in raster format, the layer with the boundary conditions where inflow is located in the upper left and outflow in the lower left. The boundary conditions are a hydrograph with a peak discharge of 6,500 ft^3/s and outflow condition is set to free outflow. The *MeshDensityLine* layer is there to refine the mesh in the mesh generation step. When you open the project you will have a project image



loaded in QGIS as shown in Figure 9.1.


9.2 Add MaximumErosionDepth layer and draw the polygon that defines the area of limited erosion

Defining the limited erosion areas involves the following steps:

1. Create the template for the *MaximumErosionDepth* layer: In the HydroBID Flood toolbar click on the *New Template Layer* button



2. Activate the checkbox *MaximumErosionDepth*, as shown in the Figure below:




Plugin to add a New Template Layer.

3. Edit the *MaximumErosionDepth* layer: In the layers panel, select the *MaximumErosionDepth* layer and in the digitization toolbar click on the *Toggle editing* button




A pencil icon will appear in the *MaximumErosionDepth* layer, indicating that the layer is in edit mode:



4. Draw the polygon of the limited erosion area: Using the *Add Feature* tool:




Draw the polygon that defines the area of limited erosion. The polygon should cover all the cells that will have limiting erosion. In this tutorial we will assume that an area on the river has the maximum erosion depth limited to 0.1 feet, at the end you should have an image similar to the one shown in the following figure:



Polygon of the area with limited erosion.

Once you finish drawing the polygon, the window to input the area parameters immediately appears. Input a maximum depth of erosion of 0.1 feet, as shown below:



Window for input the polygon parameters of MaximumErosionDepth layer.

5. Click on the *OK* button to save the parameters.


6. Save the changes to the layer by clicking on the *Save*  button of the digitization toolbar.

7. Exit the editing mode by clicking on the *Toggle editing*  button of the digitization toolbar.

9.3 Generate the mesh

Generate the mesh using the *Generate TriMesh* button





The results obtained as shown in Figure 9.5 (mesh of close to 15,000 cells).

9.4 Exporting files to HydroBID Flood

Now that you have generated the mesh and you have the other layers with the necessary data, export the files in the format required by HydroBID Flood.

1. Click on the *Export HydroBID Flood* button




2. When run the plugin a window is displayed, select the raster layer that contains the Digital Elevation Model (DEM) and the name of the project to be exported. Input the name without

any extension. For this example it will be: ‘MaxErosion’.


3. Before running the plugin activate the layer with the DEM (if it is deactivated).

   Once the plugin is executed, a window will be shown (Figure 9.6), as it should be for our example.



4. Once finished inputting the information, click on the OK button and the export process will begin.

   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.




Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


Once it is finished, HydroBID Flood will be loaded with the ‘MaxErosion.DAT’ file of the specific example.

9.5 Running the model

After exporting the files, HydroBID Flood is loaded with the project file of the 'MaxErosion.DAT' example and shows the *Control Data* panel to it as illustrated in Figure 9.7



The following Classic DIP panel is retained as a legacy values reference:




Note that the sediment transport module appears selected and displays a message warning that the file with the sediment information must be created. The procedure includes the following steps:

1. To create the '.SEDB' file with the parameters to calculate sediment transport: in the Modules list select *Sediment Transport*.

2. Enter the parameters for transport in suspension and bed load transport, for this example the *Sediment Transport Mode* checkbox for *Suspended Sediments* is deactivated and *Bed Load Sediment* is left active.


3. Add the sediment fractions to be considered: for this example add a single fraction with the

default values presented by the Hydronia Data Input Program, we will have an image similar to the one shown in the following Figure:



QGIS DIP Sediment Transport panel for limited erosion.

The following Classic DIP panel is retained as a legacy values reference:




Legacy Classic DIP HydroBID Flood Sediment Transport Module.

Leave all other parameters at their default values.

4. Click the [Save SED* Files] button and leave the default name provided, click [Save].
5. To run the model, click on the *Run HydroBID Flood* button in the lower section of Hydronia Data Input Program.
6. Click [Yes] when asked to save changes. By default it will prompt to overwrite the existing 'base.DAT', click [OK].

The window presented while running the model shows: simulation time, volume conservation error, total discharge of the liquid flow in and out and in this case also shows the sediment load

at the inlet and outlet as well as other parameters as the execution progresses (Figure 10.6).



9.6 Check the output files

HydroBID Flood creates the following files for output time interval defined in the *Control Data* panel:

'CELL_TIME_METRIC_DDDD_HH_MM_SS.TEXTOUT' (Metric Units) or

'CELL_TIME_ENG_DDDD_HH_MM_SS.TEXTOUT' (English Units)

where DDDD indicates the date, HH, hour, MM minutes and SS seconds.

Column 6 reports the changes in the elevation of the river bed with respect to the initial elevation. We can also visualize the changes in the elevation of the riverbed generating layers in vectorial format map from the aforementioned files using the *Maps of Results vs Time* plugin in QGIS, specifically the *Delta Bed Elevations* map:



In the following figure, the river elevation difference map for the end of the run. At the time 0000:02:00:00 it can be observed that the zone where the erosion was limited, does not present erosion, but deposition:




Figure 9.1 – Maps of elevation difference of the river bed between the initial time and at the end of the run.

This concludes the *Simulating bed load sediment transport* tutorial.

10 | Simulating suspended sediment transport with inflows of suspended sediment concentrations

In the Sediment Transport model you can define inflows of suspended sediment concentrations. This is useful to represent the spatial distribution of said sediments in the modeling domain. This exercise illustrates how to configure and perform a suspended sediment transport simulation using HydroBID Flood in which there is an inflow of suspended sediment concentrations using the QGIS interface. The procedure includes the following steps:

1. Open an existing HydroBID Flood project.
2. Export the project to Hydronia Data Input Program.
3. Edit the parameters in the Hydronia Data Input Program.
4. Running the model.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'SuspendedSediments' folder. This zip file is downloaded separately from your installation materials.

10.1 Open an existing project

1. Open QGIS
2. In the main menu go to *Project* > *Open…* and browse to the existing exercise folder.

This project comes with preconfigured layers: a domain outline with cells of 100m size, a the digital elevation model DEM of the river bed in raster format, the layer with the boundary conditions where inflow is located in the upper right and outflow in the lower left. The boundary conditions are a hydrograph with a peak discharge of 220000 ft^3/s and outflow condition is set to Uniform Flow Condition. When you open the project you will have a project image loaded in QGIS as shown in Figure 10.1.




Figure 10.1 – Project screen loaded in QGIS.

10.2 Exporting files to HydroBID Flood


The project is already set up within QGIS, so we can export the files to HydroBID Flood.

1. Click on the *Export HydroBID Flood* button



2. When run the plugin a window is displayed, select the raster layer that contains the Digital Elevation Model (DEM) and the name of the project to be exported.

3. Before running the plugin activate the layer with the DEM (if it is deactivated).



Plugin window to export the files to HydroBID Flood.

4. After entering all the required information, click [OK] to begin the export process.

In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.




Figure 10.2 – Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.

For the historical standalone workflow, HydroBID Flood automatically loads the project's base.DAT file after export.

10.3 Running the model

After exporting the files, HydroBID Flood loads the project file 'base.DAT' and displays the *Control Data* panel as shown in Figure 10.3




Figure 10.3 – QGIS DIP Control Data panel for suspended sediment transport.

The following Classic DIP panel is retained as a legacy values reference:




Figure 10.4 – Legacy Classic DIP Control data panel.

Note that the sediment transport module is not selected by default. The Hydronia Data Input Program should be configured as follows:

1. On the Control Data panel, click on *Sediment Transport* module. (If you have an Nvidia GPU, you can click on *HydroBID Flood GPU* under *Model Selection*.)


2. To create the '.SEDB' file with the parameters to calculate sediment transport: in the Modules list select *Sediment Transport*.

3. Enter the parameters: In this example the *Sediment Transport Mode* checkbox for *Bed Load Sediment* is deactivated and *Suspended Sediments* is left active.

4. In the *Suspended Sediment Transport* section: Uncheck the option for *Bed Fraction Evolution*.


5. Under the *Dispersion coefficient* section, give the values *0.1* for Longitudinal and *0.001* for Transversal.

6. Click on *Add Suspended Sediment Fraction* to add a single fraction with the default values presented by the Hydronia Data Input Program, we will have an image similar to the one shown in the following Figure:



QGIS DIP Sediment Transport panel for suspended sediment transport.

The following Classic DIP panel is retained as a legacy values reference:




Legacy Classic DIP HydroBID Flood Sediment Transport Module.

Leave all other parameters at their default values.

7. Click the [Save SED* Files] button and leave the default name provided, click [Save].


8. On the left-hand panel, click on *Open Boundary Conditions*.

9. In the Boundary Conditions panel, click on the entry for BC 1, Discharge vs. Time. A message should be displayed indicating that you will need to add a column for each concentration that is configured in the *Sediment Transport* module:



QGIS DIP Open Boundary Conditions panel for suspended sediment transport.

The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Message indicating that you will need to add a column for each concentration that is configured in the Sediment Transport module.


10. In the section displaying the contents of the 'Inflow_1.QVT' file, scroll to the right and add the concentrations 0.01 to each row in the *Conc.1* column.

11. Once entered, a warning message should be displayed indicating that the 'Inflow_1.QVT' file has been modified, click [Yes] to save the changes.

12. To run the model, click on the *Run HydroBID Flood* button in the lower section of Hydronia Data Input Program.

13. Click [Yes] when asked to save changes. By default it will prompt to overwrite the existing 'base.DAT', click [OK].

The window presented while running the model shows: simulation time, volume conservation error, total discharge of the liquid flow in and out and in this case also shows the sediment load at the inlet and outlet as well as other parameters as the execution progresses (Figure 10.6).



10.4 Check the output files

HydroBID Flood creates the following files for output time interval defined in the *Control Data* panel: 'cell_st_DDDD_HH_MM_SS.textout'
Where DDDD indicates the date, HH, hour, MM minutes and SS seconds.
The format for these files is as follows: The first line indicates the number of suspended sediment classes/fractions used in the ST run times 2 plus 1 (2*NSSNFRAC+1). Then follows NELEM lines with results for each cell in the triangular-cell mesh.

10.5 Generate a Concentration Map

1. Click the *Results vs Time Maps* button.
2. Select *Concentrations and Properties versus Time Maps*.
3. In the *Maps* section, select Concentration_1.
4. In the *Output Times* section, select the desired time (e.g., 0000:02:00:00).
5. Move the second desired output time to the *Output Map* section by clicking the right arrow button.
6. Click *OK* to generate the map.




Figure 10.5 – Map of suspended sediment concentration for the last time step.

This concludes the *Simulating suspended sediment transport with inflows of suspended sediment concentrations* exercise.

11 | Hydrologic simulations

The conceptual model of a hydrologic simulation with HydroBID Flood requires a series of non-overlapping polygons where the rainfall/evaporation and infiltration data will be assigned to the mesh. Only areas covered by polygons will receive rainfall or consider infiltration depending on the case. Each Rainfall/Evaporation polygon should be associated with a file containing a rainfall and evaporation time-series file. Similarly, each Infiltration polygon should correspond with a file containing the infiltration calculation method and its parameters for the polygon. The user will need to generate the rainfall and infiltration data files associated with each polygon, and copy them to the project folder prior to running the model.
This tutorial illustrates how to perform a hydrologic simulation accounting for rainfall, evaporation and infiltration. The procedure includes the following steps:

1. Create the rainfall and evaporation time series data files.
2. Create the infiltration data files.
3. Open an existing HydroBID Flood project.
4. Add the template of the *RainEvap* component layer and the rain/evaporation polygons.
5. Add the template of the Infiltration component layer and the Infiltration polygons.
6. Generate the mesh.
7. Running the model.
8. Visualize model results.


The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'RainfallInfiltrationTutorial' folder. This zip file is downloaded separately from your installation materials.

11.1 Create the rainfall and evaporation time series data file

To run a hydrologic simulation with HydroBID Flood, polygons will be created on which the rainfall/ evaporation data will be applied. The first step is to create the ASCII text files with the rainfall and evaporation time series that will be associated with each polygon. These files can be created with any text editor, such as Notepad or Wordpad. The rainfall/evaporation file has the following format:

Line 1: NPRE Number of points in the time series of rainfall and evaporation
Then follows NPRE lines containing:
Time (hr) Precipitation intensity (mm/h or in/h) Evaporation (mm/h or in/h)
The following table is an excerpt of the 'Rainfall1.dat' file that is included in the folder for this tutorial. In this example, evaporation is assumed to be zero at all times. Figure 11.1 shows the graphical representation of the rainfall time series in the 'Rainfall1.dat' file.

18
0.0 0.0 0.0
0.08 1.8 0.0
0.17 3.5 0.0
0.25 7.8 0.0
0.33 12.0 0.0
0.42 15.0 0.0
...
1.17 9.0 0.0
1.25 4.7 0.0
1.33 3.0 0.0
1.42 2.4 0.0




11.2 Create the infiltration parameters data file

To take into account infiltration, polygons will be created in which you specify the infiltration calculation method and its corresponding data. The infiltration polygons are completely independent from the precipitation polygons. Each polygon can use a different method with its associated parameters. You will need to create the infiltration ASCII text file for each polygon. These files can be created with any text editor, such as Notepad or Wordpad. The infiltration file is described in detail in the HydroBID Flood Reference Manual. For this tutorial, given that the watershed has an area with natural coverage in the upper area and another with urban use in the lower area of watershed, we will use two infiltration files using the the SCS-CN method to calculate the infiltration. File 'Infiltration1.dat' will be used for the upper watershed, and for the lower urban zone, 'Infiltration2.dat' file. Both files are provided in the folder for this tutorial.

11.3 Open an existing project

1. Open QGIS
2. On the *Project* menu click *Open…* and browse to the existing project: 'RainfallInfiltrationTutorial.qgz'. This project contains the information to simulate the rainfall runoff resulting from a 10 yr storm. The layers contained are the following:
   - Domain Outline
   - Digital Elevation Model (DEM) in raster format
   - Aerial photography
   - Polygons with the Manning's n coefficients
   - Cross section at watershed outlet
   - Outflow boundary conditions set to free outflow

   When you open the project you will have an view similar as that shown in Figure *6-2*.



Rainfall and infiltration tutorial loaded in QGIS.


11.4 Add the *RainEvap* component layer, and the rainfall/evaporation polygons

To add the *RainEvap* where the polygons are drawn with the rainfall and evaporation data, do the following:

1. To create *RainEvap* layer use the *New Template Layer* button



2. In the window check *RainEvap*, as shown in the Figure below. Then click OK:




Add Layer Template dialog with RainEvap selected.

3. Edit the *RainEvap* layer: In the layers panel, select the *RainEvap* layer and click on the *Toggle Editing* button in the digitization bar




A pencil icon will appear in the *RainEvap* layer, indicating that the layer is in edit mode:



4. Draw the polygon that demarcates the spatial distribution of rainfall and evaporation: Using the *Add Feature* tool from the digitization toolbar



draw the rainfall/evaporation polygon, as only one file will be used. The polygon should covers the entire *Domain Outline* as shown in the figure below:



Polygon with the spatial distribution of Rainfall/evaporation data.

5. Right-click to close the polygon. A dialog box will appear to enter the RainEvap Feature Attributes.

6. Input the parameters or attributes of the RainEvap polygon: Click on the browse […]button and select the 'Rainfall1.dat' file in the scenario folder.

7. Save the changes in the RainEvap layer and click the pencil icon to disable editing mode.


11.5 Add the *Infiltration* component layer, and the Infiltration polygons

To add the infiltration information, do as follows:

1. To create the *Infiltration* layer y use the *New Template Layer* button



2. In the dialog select Infiltration, as shown in the Figure below:




Add Layer Template dialog with Infiltration selected.

3. Edit the *Infiltration* layer: In the layers panel, select the *Infiltration* layer and click on the *Toggle Editing* button.




A pencil will appear in the *Infiltration* layer, indicating that the layer is in edit mode:



4. Draw the polygon that demarcates the spatial distribution of the infiltration: Using the tool Add Feature tool of the digitization toolbar, draw the infiltration polygons




Figure 11.6 shows the polygons that define the two infiltration zones of the watershed that are




based on the land use and vegetation cover.

5. Draw a polygon for the *infiltration2* area trying to maintain the shape as indicated in the previous figure and that protrudes from the polygon of the Domaine Outline as shown in the figure below:



Polygon of the infiltration2 area of the watershed.

6. Once completing the polygon, the dialog to input the parameters opens. Browse to the input file *Infiltration2.txt*, as shown below:




Window to input the parameters for the infiltration2 polygon.

7. To draw the second polygon corresponding to *infiltration2* use the snapping option as shown in the section *Advanced Digitalization/Snapping Tutorial* and there should be a polygon like the one shown in the following figure:



Polygons of the infiltration areas of the watershed.

8. Once finished drawing the polygon, enter the file name ‘Infiltration1.txt’ as shown:



Dialog to enter the parameters for the infiltration1 polygon.

11.6 Generate the mesh

The mesh is generated using the *Generate TriMesh* icon






Figure 11.11 shows the resulting mesh of about 70,000 cells.

11.7 Exporting files to HydroBID Flood

Now that once you have generated the mesh and the other layers are ready with the necessary data, you should export the files in the format required by HydroBID Flood. We will use the *Export HydroBID Flood* icon.

1. Click on the *Export HydroBID Flood* icon.




When running the export command, you need to select the raster layer that contains the Digital Elevation Model (DEM). The name of the current scenario will already be indicated in the dialog.



Export dialog.

2. Click on the [OK] button and the export process will begin. Once finished, the HydroBID Flood program will be loaded with the 'base.DAT' file.


In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


11.8 Running the model

After exporting the files, the Hydronia Data Input Program is loaded with the project file from the



'base.DAT' example and shows the *Control Data* panel as illustrated in Figure 11.13

The following Classic DIP panel is retained as a legacy values reference:



As shown above, the Rainfall Components Evaporation/Infiltration are selected in the data panel.


1. Under *Time control data* set the *Output interval for components (hrs)* to 0.1.

   If you have an nVidia GPU installed, you may select the *HydroBID Flood GPU* radial button under *Model Selection* to accelerate the model execution


2. Click [Save .DAT] to overwrite the existing 'base.dat' file.

3. Select *Rainfall/Evaporation* of the *Conponents* section in left-hand panel.


   The rainfall data contained in the 'rainfall1.txt' file will appear (Figure 11.14). In the *Infiltration* panel the data contained in the *Infiltration1* and *Infiltration2* files is shown (Figure 11.15).



The following Classic DIP panel is retained as a legacy values reference:




The following Classic DIP panel is retained as a legacy values reference:



4. Leave all other parameters at their default values.

5. To run the model, click on the *Run HydroBID Flood* button. A window will appear indicating that the model began to run. The window also report the simulation time, volume conservation error, total input and output discharge, and other parameters as the execution progresses



(Figure 11.16).

11.9 Utilizing the Cross Section Tool to review output files


1. In QGIS, click on the *Cross Section* icon.



2. The Cross Sections panel will appear on the bottom of the QGIS interface.

The outflow hydrograph can be visualized using the cross section tool as shown in Figure

11.17:



This concludes the *Hydrologic simulations* tutorial.

12 | Urban Drainage using HydroBID Flood and EPA-SWMM


This tutorial illustrates how to apply the HydroBID Flood Urban Drainage module that integrates surface flooding with EPA-SWMM storm drain model. The project objective is to assess the shallow inundation originating from a surcharging underground pipe. The procedure involves the following steps:

1. Create a SWMM application.
2. Open an existing HydroBID Flood model.
3. Import the surface-storm drain exchange points from the'.INP' SWMM file.
4. Generate the mesh.
5. Export the files of HydroBID Flood.
6. Run the model.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'UrbanDrainageTutorial' folder. This zip file is downloaded separately from your installation materials.

The pipe is modeled in 1D and connected to the 2D mesh through a manhole. The modeled area is approximately 0.4 km by 0.96 km (see Figure 12.1). A storm drain of circular section of $1.4m$ in diameter and 1340 m in length is assumed to run through the modeled area. The pipe Manning's roughness is set to n=0.017. An inflow boundary condition is applied at the upstream end of the pipe, illustrated in Figure 12.2. A free outfall is considered as downstream boundary condition. A base initial flow of 1.6 m^3/s is set as uniform initial condition. A surcharge is expected to occur at a vertical manhole of 1 m^2 cross-section located 467 m from the top end of the culvert at the coordinates (x=264,896 m,y=664,747 m). The profile geometry of the culvert is given in Table [pipe012] and

shown in Figure 12.3.






Figure 12.1 – Inflow hydrograph applied at upstream end of storm drain.

c c c c c Node	Distance from upstream inlet (m)	Invert level (m)	Reach length (m)	X	Y
N1	0	39.17	-	264896.000	664747.000
N2_manhole	467	29.46	467	264896.000	664747.000
N3	571	27.70	104	265633.232	664154.002
N4	677	26.37	106	266474.164	663829.787
N5	877	25.70	200	267730.496	663302.938
N6	991	24.64	114	268470.111	662978.723
N7	1145	24.29	154	269533.941	662725.431
Out1	1340	23.49	195	271874.367	661752.786





Figure 12.2 – Storm drain profile.

12.1 Storm drain configuration in EPA-SWMM


> **Note**
>
> If you want to skip this step, you may want to use the SWMM 'base.INP' in the tutorial folder. In that case, please go to section 12.1.1.

1. Open the SWMM application.

2. The first step consists in setting the position of all the nodes that conforms the drainage network by means of the button *Add a junction node*:




On the *Study area map* window, click as many times as nodes should be added to the network. In this project there will be 8 nodes. Note that the position of the nodes is schematic:



3. Configure the node data by double-clicking on each node. The node properties window should appear:

   image image


   In this example, the most relevant parameters are: *Name*, *X-* and *Y-Coordinates*, *Inflows*, *Invert elevation* and *Max. depth*. The only inflow nodes are *N1* and *N2_manhole*. Node *N2_manhole* should have *Max. depth=2 m*. Node *N1* is the discharge input and should follow the time series given in Figure 12.2.




   The time series can be inserted point-by-point or read from file. On the other hand, node *N2_manhole* will be the connection with the surface domain and the baseline values should be 0.0:

   image image


   The outfall node *Out1* should be configured as *free*:




4. Join the nodes by means of the *Add a conduit link* tool:



The result should look like the following figure:



5. Configure the link properties by double-clicking on each one:



   The most relevant properties are: *Name*, *Inlet node*, *Outlet node*, *Shape*, *Max. depth*, *Length*, *Roughness* and *Initial flow*.

6. Once the network is completely configured, the project should be saved in order to generate the '.INP' file that should be similar to the one shown below.

```
[EVAPORATION]
;;Data Source      Parameters
;;--------------- ----------------
CONSTANT          0.0
DRY_ONLY          NO

[JUNCTIONS]
;;Name            Elevation   MaxDepth    InitDepth   SurDepth    Aponded
;;--------------- ---------- ---------- ---------- ---------- ----------
N1                39.17       0           0           0           0
N2_manhole        29.46       2           0           0           0
N3                27.7        0           0           0           0
N4                26.37       0           0           0           0
N5                25.7        0           0           0           0
N6                24.64       0           0           0           0
N7                24.29       0           0           0           0

[OUTFALLS]
;;Name            Elevation   Type        Stage Data       Gated    Route To
```

```
;;-------------- ---------- ---------- ---------------- -------- ----------------
Out1             23.49      FREE                        NO

[CONDUITS]
;;Name           From Node          To Node            Length     Roughness
InOffset     OutOffset    InitFlow     MaxFlow
;;-------------- ---------------- ---------------- ---------- ---------- ---------- -------
L1               N1                 N2_manhole       467        0.017
0            0            1.6          0
L2               N2_manhole         N3               104        0.017
0            0            1.6          0
L3               N3                 N4               106        0.017
0            0            1.6          0
L4               N4                 N5               200        0.017
0            0            1.6          0
L5               N5                 N6               114        0.017
0            0            1.6          0
L6               N6                 N7               154        0.017
0            0            1.6          0
L7               N7                 Out1             195        0.017
0            0            1.6          0

[XSECTIONS]
;;Link           Shape        Geom1            Geom2      Geom3      Geom4
Barrels      Culvert
;;-------------- ------------ ---------------- ---------- ---------- ---------- ----------
L1               CIRCULAR     1.4              0          0          0
1
L2               CIRCULAR     1.4              0          0          0
1
L3               CIRCULAR     1.4              0          0          0
1
L4               CIRCULAR     1.4              0          0          0
1
L5               CIRCULAR     1.4              0          0          0
1
L6               CIRCULAR     1.4              0          0          0
1
L7               CIRCULAR     1.4              0          0          0
1

[INFLOWS]
;;Node           Constituent      Time Series      Type     Mfactor  Sfactor
Baseline Pattern
```

```
;;-------------- ---------------- ---------------- -------- -------- -------- -------
N1               FLOW             discharge_inflow FLOW     1.0      1
N2_manhole       FLOW             ""               FLOW     1.0      1.0
0.0

[TIMESERIES]
;;Name            Date       Time       Value
;;-------------- ---------- ---------- ----------
discharge_inflow             0:00       1.6
discharge_inflow             0:02       1.6
discharge_inflow             0:04       1.6
discharge_inflow             0:06       1.6
discharge_inflow             0:08       1.61644
discharge_inflow             0:10       1.6336
discharge_inflow             0:12       1.65472
discharge_inflow             0:14       1.67188
discharge_inflow             0:16       1.68904
discharge_inflow             0:18       1.70488
discharge_inflow             0:20       1.71808
discharge_inflow             0:22       1.71808
discharge_inflow             0:24       1.7392
discharge_inflow             0:26       1.75636
discharge_inflow             0:28       1.77352
discharge_inflow             0:30       1.7986
discharge_inflow             0:32       1.82764
discharge_inflow             0:34       1.8448
discharge_inflow             0:36       1.88704
discharge_inflow             0:38       1.92136
discharge_inflow             0:40       1.95436
discharge_inflow             0:42       1.98868
discharge_inflow             0:44       2.02168
discharge_inflow             0:46       2.056
discharge_inflow             0:48       2.09824
discharge_inflow             0:50       2.1484
discharge_inflow             0:52       2.19988
discharge_inflow             0:54       2.25928
discharge_inflow             0:56       2.32264
discharge_inflow             0:58       2.3728
discharge_inflow             1:00       2.4784
discharge_inflow             1:02       2.56288
discharge_inflow             1:04       2.66056
discharge_inflow             1:06       2.77012
discharge_inflow             1:08       2.8876
discharge_inflow             1:10       3.0064
```

discharge_inflow	1:12	3.17536
discharge_inflow	1:14	3.29416
discharge_inflow	1:16	3.44992
discharge_inflow	1:18	3.61888
discharge_inflow	1:20	3.78784
discharge_inflow	1:22	3.9568
discharge_inflow	1:24	4.168
discharge_inflow	1:26	4.33696
discharge_inflow	1:28	4.50592
discharge_inflow	1:30	4.67488
discharge_inflow	1:32	4.83988
discharge_inflow	1:34	4.99168
discharge_inflow	1:36	5.16064
discharge_inflow	1:38	5.27944
discharge_inflow	1:40	5.41012
discharge_inflow	1:42	5.54476
discharge_inflow	1:44	5.67148
discharge_inflow	1:46	5.77312
discharge_inflow	1:48	5.89984
discharge_inflow	1:50	6.00148
discharge_inflow	1:52	6.10312
discharge_inflow	1:54	6.1876
discharge_inflow	1:56	6.24096
discharge_inflow	1:58	6.28111
discharge_inflow	2:00	6.28111
discharge_inflow	2:02	6.24096
discharge_inflow	2:04	6.1876
discharge_inflow	2:06	6.10312
discharge_inflow	2:08	6.00148
discharge_inflow	2:10	5.89984
discharge_inflow	2:12	5.77312
discharge_inflow	2:14	5.67148
discharge_inflow	2:16	5.54476
discharge_inflow	2:18	5.41012
discharge_inflow	2:20	5.27944
discharge_inflow	2:22	5.16064
discharge_inflow	2:24	4.99168
discharge_inflow	2:26	4.83988
discharge_inflow	2:28	4.67488
discharge_inflow	2:30	4.50592
discharge_inflow	2:32	4.33696
discharge_inflow	2:34	4.168
discharge_inflow	2:36	3.9568
discharge_inflow	2:38	3.78784

```
discharge_inflow        2:40        3.61888
discharge_inflow        2:42        3.44992
discharge_inflow        2:44        3.29416
discharge_inflow        2:46        3.17536
discharge_inflow        2:48        3.0064
discharge_inflow        2:50        2.8876
discharge_inflow        2:52        2.77012
discharge_inflow        2:54        2.66056
discharge_inflow        2:56        2.56288
discharge_inflow        2:58        2.4784
discharge_inflow        3:00        2.3728
discharge_inflow        3:02        2.32264
discharge_inflow        3:04        2.25928
discharge_inflow        3:06        2.19988
discharge_inflow        3:08        2.1484
discharge_inflow        3:10        2.09824
discharge_inflow        3:12        2.056
discharge_inflow        3:14        2.02168
discharge_inflow        3:16        1.98868
discharge_inflow        3:18        1.95436
discharge_inflow        3:20        1.92136
discharge_inflow        3:22        1.88704
discharge_inflow        3:24        1.8448
discharge_inflow        3:26        1.82764
discharge_inflow        3:28        1.7986
discharge_inflow        3:30        1.77352
discharge_inflow        3:32        1.75636
discharge_inflow        3:34        1.7392
discharge_inflow        3:36        1.71808
discharge_inflow        3:38        1.71808
discharge_inflow        3:40        1.70488
discharge_inflow        3:42        1.68904
discharge_inflow        3:44        1.67188
discharge_inflow        3:46        1.65472
discharge_inflow        3:48        1.6336
discharge_inflow        3:50        1.61644
discharge_inflow        3:52        1.6
discharge_inflow        3:54        1.6
discharge_inflow        3:56        1.6
discharge_inflow        3:58        1.6
discharge_inflow        5:00        1.6

[REPORT]
;;Reporting Options
```

```
INPUT      NO
CONTROLS   NO
SUBCATCHMENTS  ALL
NODES  ALL
LINKS  ALL

[TAGS]

[MAP]
DIMENSIONS  260000.000  660000.000  270000.000  670000.000
Units      Meters

[COORDINATES]
;;Node            X-Coord            Y-Coord
;;--------------  ------------------ ------------------
N1                264903.824         664753.843
N2_manhole        264896.000         664747.000
N3                265633.232         664154.002
N4                266474.164         663829.787
N5                267730.496         663302.938
N6                268470.111         662978.723
N7                269533.941         662725.431
Out1              271874.367         661752.786

[VERTICES]
;;Link            X-Coord            Y-Coord
;;--------------  ------------------ ------------------
```

12.1.1 Starting QGIS

Start the QGIS software. After loading we will have a window similar to the one shown below:




Figure 12.3 – QGIS interface.

12.1.2 Start a new HydroBID Flood project

1. In the HydroBID Flood toolbar, click on the *New HydroBID Flood Project* button


   

   to start a new HydroBID Flood project. A dialog window appears where you select the layers that will be created, the Coordinate Reference System (CRS), and the directory path where the layers will be saved. This example will use the basic layers: *Domain Outline*, *Manning N*, and *BoundaryConditions*

2. Select *None* in the Layers dropdown menu.

3. Select the *Projection* button.


4. In the Filter textbox, type 7405 and select the *Coordinate Reference System* as shown:



Coordinate Reference System Selector dialog window.

5. Click OK.


6. The Coordinate Reference System (CRS) EPSG code: 7405 should be selected, and the dialog window will look like this:



Create New HydroBID Flood Project.

7. Click the "…" button to provide a path to store the project files in the *Project Directory* textbox. For this example you may browse to the UrbanDrainageTutorial folder.

8. After clicking OK, the layer templates are created, and displayed on the *Layers Panel*:



Layers created for the project.

HydroBID Flood will use the unit system as that defined in the projection you selected. If the projection has coordinates in meters, units will be set to Metric. If the projection coordinates are in feet, units will be set to English.


9. On the QGIS *Project* menu, click *Save*, to save the project in the same directory that you previously selected in the *Create New Project* dialog above.

12.1.3 Load elevation data


HydroBID Flood uses elevation data in raster format. To load an ASCII grid file, from the *Layer* menu, click *Add Layer*, and then click *Add Raster Layer…* You may also click the *Add Raster Layer* button:



Search for TEST8BDEM.ASC in the UrbanDrainageTutorial/base folder:




1. Click Add, assign the EPSG:7405 projection code to the file, and raster will be displayed on the




screen, by default it is rendered in gray gradient as shown in Figure 19.7.

Right-clicking on the label of the created layer and selecting *Properties* allows you to change the rendering style for a more informative color palette.



Window to change the raster layer render style.

And now the raster layer is displayed with the new color palette selected:




Digital elevation model with color render.

It is convenient to move the raster layer created to the end of the list of layers, thus it does not interfere with the display of other layers.


12.1.4 Import the surface-storm drain exchange node connections from the SWMM .INP file

To connect the surface water mesh with the storm drain components, we will import the exchange nodes from the '.INP' file created in the first part of this tutorial. For that we will use the *Import EPA-SWMM INP file* command from the HydroBID Flood tools drop down icon:




Import EPA-SWMM INP file command

Select the 'base.INP' file and a message will indicate the transfer was successful:



.INP successfully loaded

You will note that there is a new *StormDrain* layer created and the imported exchange nodes are displayed:



Surface water-SWMM exchange nodes.

12.1.5 Create the limits of the modeling area

The limits of the modeling area are defined using a polygon on the *Domain Outline* layer. To create it do as follows:

1. Click the *Domain Outline* layer to activate it and then click *Toggle Editing* (pencil) in the toolbar:




Menu buttons for digitization toolbar.

2. This activates the rest of the editing buttons. Now click the *Add Feature* tool which is the bean looking polygon.




Proceed to delineate the outline of the polygon by marking the vertices clicking with the left mouse button:



Modeling area delimitation on the Domain Outline layer.

Make sure that the polygon is contained within the limits of the raster layer since HydroBID Flood will not extrapolate elevations to areas that are outside of the available data on the raster layer. Also, the SWMM exchange nodes should be inside the *Domain Outline* polygon.

3. To finalize and close the polygon, right-click anywhere on the map view area. A dialog window to input the cell size attribute of the newly created polygon. The value for the reference size of the mesh cell is indicated. Enter a value of 10 m.



CellSize defined for the Domain Outline layer.

Now click on *Toggle Editing* button to deactivate the layer Edit mode and save the changes.



The *Domain Outline* is now complete.




Figure 12.4 – Domain Outline layer.

12.1.6 Assigning Manning's n


To assign Manning's n roughness values, we will enter polygons with given n's. There can be as many polygons as those required to reproduce the spatial variability of this parameter. In this example, a single polygon will be drawn for the entire area.

1. Select the *Manning N* layer and click the *Toggle Editing* button:




2. Draw the polygon around the entire domain taking care that it covers all the cells.

   You should have an image like the one shown below:



   Editing the Manning N layer.

3. Close the last vertices on the polygon by right-clicking on the desired position. The following dialog window is presented where you must input the Manning's n value associated to the polygon. For this case, enter 0.03:



   Dialog to input Manning N Feature Attributes.

4. Click the *Save* button



and then click the Editing Tool button



to deactivate editing mode.

12.1.7 Imposing the boundary conditions

By default all boundaries are closed unless we set open boundary conditions. Since in this project flow is input from the storm drain, we will set only outflow conditions. To define the boundary conditions draw a polygon that includes the nodes or vertices at the left end of the mesh as indicated in the figure:




Figure 12.5 – Polygon that covers the nodes defining the Outflow boundary condition segment.


1. Select the *BoundaryConditions* layer in the Layers panel.
2. Click the Toggle Editing button to add the polygons that are going to indicate the nodes on which the inflow and outflow conditions are established.



3. To finish the polygon, right-click on desired location. A window to enter the attributes of the newly created polygon is displayed.

4. The window contains a list to select the name of ID of this BC (*Boundary Cond. ID*), set Id to OUTFLOW condition, and from the list of boundary condition Types select *Free Outflow*.

   Enter the data as shown in Figure 12.21 below:



   Outflow Boundary Condition.

5. Click the Save  button:

6. Click the Toggle Editing  button to exit editing mode.

12.1.8 Generating the triangular-cell mesh

Now that the *Domain Outline* has been set, the Manning's n entered, and the SWMM nodes have been imported, we can proceed to create the mesh using the GMSH program.

To run the plugin, on the the *Plugins* menu, click *Generate TriMesh*, or click on the icon:



The following figure shows the generated mesh. You will also see in the Layers panel two new layers: *Trimesh* and *Trimesh_point*:




Figure 12.6 – Resulting mesh.

Before using the *Export* plugin, save the QGIS project. To accomplish this, from the *Project* menu, click *Save*. Name the project file 'UrbanDrainageTutorial.qgz'.

12.2 Exporting the files

Once the layers with the input information to the model have been created, the next step is to export from QGIS the data files required by the HydroBID Flood model.

1. Run the *Export HydroBID Flood* plugin



2. A dialog window is presented. We must indicate the raster layer of the Digital Elevation Model (DEM), as this layer is not created by the plugin and its name may be different.

3. Using the "…" button, select the path, and enter the file name. Please, ensure that the path is the same as that previously selected, and the one corresponding to the '.qgz' project file.


4. Click OK.



Export HydroBID Flood dialog.

The plugin will begin to process the information. A message bar at the top will indicate the approximate progress of the process.


In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


Once the process of creating the files with the input data is finished, the Hydronia Data Input Program is opened automatically and a dialog window is presented with the model project to run. In this case: 'base.DAT' should already be set.

Then the window with the input parameters of HydroBID Flood is presented, as shown in the image below:




QGIS DIP Control Data panel for the Urban Drainage tutorial.

The following Classic DIP panel is retained as a legacy values reference:




Legacy Classic DIP Hydronia Data Input Program window.

Enter 5 hours for the Simulation time and click on the Storm Drain EPA-SWMM panel. Enter for the N1 node CD = 0 since we don't want exchange with that inflow node to the conduit.



QGIS DIP Storm Drain EPA-SWMM panel.


The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Storm Drain Dialog.


5. Click [Save .LWSMM] and overwrite the existing file, for this tutorial the filename will be the name of the project when it was exported with the '.lwsmm' extension.

6. Click the *Run HydroBID Flood* button to run the model. The model will show a window reporting on the model progress.



Morel Report Window.

When the run finishes, close the window and you can import results back in QGIS to prepare maps and animations. An example of the maximum depths is shown below:



Maximum depths.

This concludes the *Urban Drainage using HydroBID Flood and EPA-SWMM* tutorial.

13 | Simulating a tailings dam failure with HydroBID Flood MT

This tutorial will show how to set up a tailings dam failure simulation with the HydroBID Flood model with the Mud and Tailings Flow Module (MT) using the QGIS interface. The exercise consists of modeling a tailings dam failure flood and creating results maps for the impacted areas. The data is based on the Brumadinho dam disaster occurred on 25 January 2019 when a tailings dam at the CA3rrego do FeijAśo iron ore mine, east of Brumadinho town, in Minas Gerais, Brazil, suffered a catastrophic failure.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'BrumadinhoHBF' folder. This zip file is downloaded separately from your installation materials.





Figure 13.1 – Files with data required for the example.

13.1 Start a new project for a tailing dam break simulation

1. To create a new HydroBID Flood project, open QGIS and click on the *New HydroBID Flood Project* button  in the toolbar. A dialog window appears where you select the layers that will be created, the name of the *Senario*, the *Coordinate Reference System (CRS)*, and the directory path where the layers will be saved. This example will use the layers: *Domain Outline*, *Manning N*, *BoundaryConditions*, *MeshDensityLine*, and *InitialConcentrations*.


2. Select *None* in the Layers drop-down menu, then click the *MeshDensityLine* and the *Initial Concentrations* check boxes.

3. Click the *Projection* button and in the *Filter* text box, type *31983* and select the *Coordinate Reference System* and click OK as shown:




Coordinate Reference System Selector dialog window.

4. Click the  button to provide a path to store the project files in the *Project Directory* text box. This will be the folder where the model will write all results and output files. Browse to the tutorial directory in the location where the files were extracted, in the 'BrumadinhoHBF' folder, then click Select folder. The dialog window should look like the following:



Create new project window.

5. After clicking OK, the layer templates are created, and displayed on the *Layers Panel*



Layers created for the project.


On the QGIS *Project* menu, click *Save*, to save the project in the same directory that you previously selected in the *Create New Project* dialog above.

13.2 Load elevation data

In this tutorial we will use two *Digital Elevation Model* or *DEM* raster files that contain the terrain elevation data and tailings dam volume data.

1. To load the DEMs, click the *Add Raster Layer* button  . You may also use the QGIS shortcut *Control+Shift+R*.

2. In the dialog search for the tutorial folder and select the ‘RasterBRUMADINHO.tif’ and ‘RasterDAM10.tif’ files as shown:




Dialog to create a layer from a raster file.

3. Click *Add* and then *Close*.


4. Click on the *RasterBRUMADINHO* layer. Use the *Zoom to Layer* button  to center the image.

The raster will be displayed on the screen, by default it is rendered in gray gradient as shown.



Digital elevation model in raster format.

Right-clicking on the label of the new raster layer and selecting *Properties*, in the *Symbology* panel you can change the *Render type* for a more informative palette such as *Hillshade* for instance.



Digital elevation model with Hillshade render.

You may move the raster layer by dragging it to the end of the list of layers to avoid that it would hide or interfere visually with the other layers.

13.3 Create the limits of the modeling area


We define the limits of the modeling area drawing a polygon on the *Domain Outline* layer. To create it do as follows:

1. Click the *Domain Outline* layer to activate it and then click *Toggle Editing* (pencil) in the toolbar 

2. Click the *Add Polygon Feature* tool  . Proceed to delineate the outline of the polygon by clicking the vertices with the left mouse button.

3. To finalize and close the polygon, right-click on the map view area. A dialog window to input the cell size attribute of the newly created polygon will appear. The *CellSize* value for the reference size of the mesh cell is indicated. Enter a value of 50 m.

   The Domain Outline should look similar to the following figure:



   Domain Outline polygon.


4. Save the polygon by clicking the *Save Layer Edits* button  .

5. Click on *Toggle Editing* button to deactivate the layer Edit mode 

13.4 Create more detail for the mesh down the main flow area

Once the *Domain Outline* is created, a *Mesh Density Line* will provide the necessary detail down the main channel for more accuracy.


1. Select the *MeshDensityLine* layer making sure it is activated as shown



and click the *Toggle Editing* button  .

2. Click the *Add Line Feature*  button then Left-click to draw the points down the middle of the channel all the way to the river entrance at the bottom of the *Domain Outline*.


3. Right-click to finish the line. A dialog requesting input for the *MeshDensityLine Feature Attributes* will appear. Input *25* as the *CellSize* for the *MeshDensityLine* layer. The first line should look as follows:



First mesh density line.

Another line will need to be drawn to finish adding detail down the main path on the river in the south.

4. Click the *Add Line Feature*  button then Left-click to draw the points starting from the the south-western part of the *Domain Outline* along the riverbed and right-click to finish the line, joining it to the first line as follows:




Second mesh density line.

5. Right-click to finish the second line. A dialog requesting input for the *MeshDensityLine Feature Attributes* will appear. Input *25* as the *CellSize* for the *MeshDensityLine* layer.

6. Save the polygon by clicking the *Save Layer Edits* button  .

7. Click on *Toggle Editing* button to deactivate the layer Edit mode 

   The finished *MeshDensityLine* layer should look as follows:



Finished MeshDensityLine layer.

13.5 Generating the triangular-cell mesh

Now that the *Domain Outline* and *Mesh Density Line* layer have been created, proceed to generate the mesh by clicking on the *Generate Trimesh*  button.

The following figure shows the generated mesh. You will also see in the Layers panel the new layer: *Trimesh*




Figure 13.2 – Triangular mesh generated for the tailings dam break tutorial.


13.6 Setting up the boundary conditions

Here we will explain how to enter boundary conditions that are needed in any inflow or outflow sections of the model area where flow can enter or leave the mesh. In this tutorial we will have one inflow and one outflow condition.

We first enter the inflow boundary condition imposing a hydrograph (discharge vs time).

1. Select the *BoundaryConditions* layer in the Layers panel.

2. Click the *Toggle Editing* button  to add the polygons that will indicate the open boundary segments where inflow and outflow conditions are imposed. Draw a polygon at the bottom end of the mesh as indicated in the figure:



Polygon that covers the nodes defining the Inflow boundary condition segment.


3. To finish the polygon, right-click on desired location. A window to enter the attributes of the newly created polygon is displayed.

   The exact form of the polygon is not important. You only need to make sure that the polygon covers the segment length at which you want to impose the condition. All cells falling within that polygon will be open boundary cells.


4. In the *Boundary Cond. ID* enter the desired name or leave the default.

5. Select *2. Discharge vs. Time* from the *Type of Open Boundary* list.

6. Click *Import BC File* button, and search for the 'inlet1.QVT' hydrograph file as shown below:



Inflow boundary condition parameters.




Hydrograph loaded from the 'inlet1.QVT' file.

7. Click *OK* to close the dialog and then click *Save Layer Edits*  .


All boundary condition files, such as 'inlet1.QVT' in this tutorial, need to be in the same directory as all the other project files.
Now we will enter an free outflow condition where the fluid will be let to flow out from the mesh.

1. Click the *Add Polygon Feature* tool  . Proceed to delineate the outline of the polygon by clicking the vertices with the left mouse button. Draw the polygon defining the outflow boundary area at the downstream end of the river as shown:



Polygon that defines the outflow boundary condition segment.

2. Right click to close the polygon. A dialog window will appear to enter the parameters. Select the condition type *Uniform flow condition* and set So to 0.005. The dialog should look like the following:




Parameters for the free outflow open boundary condition.

3. Save the changes made to the layer by clicking the *Save Layer Edits* button  .

4. Deactivate editing mode by clicking on the *Toggle Editing* button  .

   The figure below shows how the *BoundaryConditions* layer should look:




Polygons that define the inflow and outflow boundary conditions.

13.7 Assigning Manning's n

Manning's n is the parameter determining the bed roughness. The model requires that all cells in the model area have a defined n. In a project application we should have n's that vary through the mesh since variable vegetation and terrain characteristics will have different roughness. However, for simplicity, in this tutorial we will assume a single n.


1. Select the *Manning N* layer and click the *Toggle Editing* button  .

2. Click the *Add Polygon Feature*  to draw a polygon that covers the entire domain. The polygon may extend beyond the mesh area as shown:



Manning N layer.

3. Close the polygon by right-clicking on the end vertex and enter a Manning's n equal to 0.035:



Dialog to input ManningN.


4. Click *Save Layer Edits*  , and then click the *Toggle Editing* button  to deactivate editing mode.

13.8 Providing the Initial Concentrations for the tailings material

The HydroBID Flood MT model allows defining initial volume concentrations that vary in space. In order for the model to assign this initial state, one or more polygons must be drawn over the tailings raster or initial water surface elevation polygon. This polygon will then be assigned a data table attribute that gives the concentrations for each sediment class.

1. Select the *InitialConcentrations* layer in the *Layers* and click the *Toggle Editing*  button


2. Click the *Add Polygon Feature*  button and draw the polygon, keeping within the edges of the *RasterDAM10* raster:



Initial Concentrations polygon.

3. An *InitialConcentrations - Feature Attributes* dialog will appear. On the *Initial Concentrations File* line click the  Browse button to select the 'Deposit_Initial.txt' file from the project folder '\ExampleProjects\BrumadinhoHBF\base\' folder and then click *OK*.

4. The dialog should look like the following:



Initial Concentrations - Feature Attributes dialog.

5. Save the changes made to the layer by clicking the *Save Layer Edits* button  .
6. Click the *Toggle Editing*  button to disable editing mode.


Save the QGIS project using the *Save Project* button or by using the *Project* menu. Name the project file 'Brumadinho.qgs'.

13.9 Exporting the project from QGIS to HydroBID Flood

Once the layers with the input data to the model have been created, we need to export data files required to run HydroBID Flood.

1. In the HydroBID Flood plugin toolbar, click the *Export files for HydroBID Flood* button and select *Export HydroBID Flood …*
2. In the export dialog window indicate the *Project Name*, *Brumadinho* in this tutorial.
3. In the drop-down menu for *DEM Single Raster* select *RasterBRUMADINHO*
4. Click on the *Options* arrowhead to view the additional parameters for the export.
5. under *DEM (Single Raster)* make sure *RasterBRUMADINHO* is selected in the dropdown menu.
6. Click to enable the checkbox for *Using Initial WSE Raster Layer*, then on the drop down menu select the *RasterDAM10* as your *InitialWSE* layer.


   Your *Export HydroBID Flood* dialog window should look like this:



Parameters for the Export to HydroBID Flood dialog.

7. Click *OK*.

   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.

13.10 Configure final model parameters in the Hydronia Data Input Program (DIP).

Once the model files have been created, the Hydronia Data Input Program will appear automatically with the main control data file loaded, in this case: 'Brumadinho.DAT'.

13.10.1 Control Data Panel


The following parameters will need to be changed as indicated:

1. In the *Control Data* panel under the *Time control data* section, Set the *Output interval (hrs.):* to *0.01*.

2. In the *Modules* section click the *Mud/Tailings Flow* radial button.


   Optional If you have an nVidia graphics card installed on the system, you can enable the *HydroBID Flood GPU* under the *Model Selection* section to accelerate the computation speed for the simulation.

   The *Control Data* panel should look like the following:



QGIS DIP Control Data panel for the Brumadinho tailings tutorial.

The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Hydronia Data Input Program window with Control Data parameters for the tailings dam break tutorial.

3. Click the *Save .DAT* button. Click Save again in the dialog box and click *Yes* to replace the existing file.

13.10.2 Mud/Tailings Flow Panel

The *Mud/Tailings Flow* module needs to be configured with the tailings properties and other rheological parameters. Please do the following:

1. Click on the *Mud/Tailings Flow* on the left side panel to activate it.

2. In the *Mud/Tailings Flow* panel, click the *Open .MUD* button.


3. A dialog will appear asking for a file ending with the '.MUD' extension. Browse for the file '\ExampleProjects\BrumadinhoHBF\base\brumDam.MUD' and click *Open*.

   You will now see that the panel has changed most of the parameters. More importantly, the *Variable properties-Erosion-Deposition Model* has been enabled, and there are six sediment classes loaded. Take some time to familiarize yourself with the parameters.

   The parameters that have been loaded need to be saved with the same name as the project name so that the model will use it upon execution.


4. Click the *Save .MUD* button and the Scenario name 'base.MUD' should already be set. Click *Save*.

   The *Mud/Tailings Flow* panel should look like the following:



QGIS DIP Mud/Tailings Flow panel for the Brumadinho tutorial.

The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Hydronia Data Input Program window with Mud/Tailings Flow parameters for the Brumadinho Tutorial.

13.10.3 Providing the Viscosity and Yield Stress data for Variable properties-Erosion-Deposition Model

When selecting to use the *Variable properties-Erosion-Deposition Model* in this tutorial, data tables for the volume concentrations relationship with Viscosity and Yield Stress need to be provided. These files are already prepared for this tutorial, and must be copied into the Scenario folder as follows:

1. In File Explorer browse to the location of the project folder '\ExampleProjects\BrumadinhoHBF\'
2. Select the following files from the folder: 'YieldStressVsCv3.txt, ViscosityVsCv3.txt'
3. Copy the files into the Scenario folder '\ExampleProjects\BrumadinhoHBF\base\'

13.10.4 Updating the Inflow Boundary Condition File

It is critical to update the *Open Boundary Conditions* data file with additional columns of data that represent the new sediment classes. By default this file contains a table of time and discharges, but the model requires for all inflow conditions the volume concentration for each sediment or material class. In case of water flow, all concentrations must be set to 1. To update it do the following:


5. Click on the *Open Boundary Conditions* under *Components* in the side panel of the Hydronia Data Input Program.

6. Click on the cell in the first table that contains the 'inlet1.QVT' variable:

Group	BC Type	File
1	Rating Table (WSE vs Discharge) (BCType 9)	inlet1.QVT
2	Free Outflow (BCType 11)	(No File)

Section containing table with Boundary Conditions set for this run.


Upon clicking the cell, a dialog box should appear that will allow us to automatically update the existing data table in the 'inlet1.QVT' file with the additional rows needed, and setting each to 0:



Dialog for correcting the Boundary Conditions file automatically.

7. Click *Yes* to update the 'inlet1.QVT' file.

You can verify the contents have been updated by scrolling to the right in the file contents section or by opening the '\ExampleProjects\BrumadinhoHBF\base\inlet1.QVT' file in Windows Explorer. Your Inlet1.QVT file should look like the following figure:



Contents of the updated Inlet1.QVT file.


13.11 Running the model

The simulation is now ready to run. Proceed as follows:

1. Click on *Control Data* in the side panel of the DIP and then click the *Run HydroBID Flood* button at the bottom.

2. The DIP will ask to save changes to the .DAT file, click *No*.

   A few windows should appear, the last one will be the graphical model windows that displays the status of the model. When the model is finished running, it should look as follows:




   HydroBID Flood model execution window.

3. Click Close and let the program finish writing the remaining output files.

13.12 Generating maps for the Mud/Tailings Flow module

Once the model has finished running we can create maps for various outputs. This tutorial will focus on some of the specific maps that can be generated once the Mud/Tailings module with variable properties-erosion deposition enabled.


1. In QGIS , in the HydroBID Flood plugin toolbar, click on the drop down menu for *Results vs Time Maps* and select *Concentrations and Properties vs Time Maps*




Concentrations and Properties vs Time button in HydroBID Flood Plugin toolbar.

The *Concentrations and Properties vs Time Maps* window will provide maps for each *Sediment class*, labeled *Conc_#* under the *Maps subsection*. Users can also create maps for each of the variables in the list.

2. Select one of the *Maps*, then select an *Output Times* of interest. You can hold *Control* key while clicking on multiple *Maps* and / or *Output Times*.

3. Once all outputs of interest are selected, click on the *Right Arrow* button 

to move them to the *Output Maps* subsection.



Concentrations and Properties vs Time Maps window.

4. Click the OK button to generate the maps.

The *Layers* panel on the left side will have a group named *OUTPUT RESULTS* where the resultant map or maps will be placed.




Figure 13.3 – Results map of Conc_1 at hour 2.

Repeat these steps to create maps for each of the concentrations if desired.

13.13 Generating animations for the Mud/Tailings Flow module

An animation can best illustrate the mud / tailings flow over time. This section will show how to generate results for the specific variable properties-erosion deposition enabled model outputs.
On the QGIS *Project* menu, click *Save*, to save the project in the same directory that you previously selected in the *Create New Project* dialog above. This is required for the *Animations* panel to function.




1. Start by activating the *Animations* panel in the HydroBID Flood plugins toolbar

   A panel will appear below the *Layers* panel on the bottom left.

2. Click on the *Select layer* drop-down menu and select *Mud/Tailings Flow*.

3. Click *Add Layer*. A dialog box will appear asking for the specific Animation we would like to create:




HBF Animation dialog window.

4. Click on the drop-down menu to see the available outputs. They will be the same as the ones from *Concentrations and Properties vs Time Maps* plugin.

5. Choose any of these and click OK.


6. Select the output range desired, or just leave the default for the entire range of output intervals. Click OK

   There is a status bar underneath the *Select layer* drop-down showing the progress of the animation generation. When it is finished, the layer previous choice of animation will appear in the box underneath the status bar.



HBF Animation panel indicating the status bar and generated animation layer.

7. Click and hold to drag the newly created *ANIMATION* group in the *Layers* panel and move it above the Raster layers so that the animation will be visible.

8. Click on the layer that was generated in the *HydroBID Flood Animation* panel then click the *Play* button  to view the animation.

   Repeat these steps to create animations for each of the concentrations if desired.

This concludes the tutorial for Simulating tailings dam Failures utilizing the Mud/Tailings Flow module in HydroBID Flood.

14 | Simulating Pollutant Transport

HydroBID Flood contains the *Pollutant Transport* module that simulates the movement and transformation of pollutants in a water body. It can account for various processes that affect the fate of pollutants, such as:

- Dissolved substance transport (Solutes)
- Advection-Dispersion-Reaction
- Thermal analysis
- Decay over time
- Multiple pollutants
- Reaction rates between pollutants

In this tutorial we will go through the step-by-step process of creating a simple scenario with pollutants on the Magdalena River in Colombia to show how the model is used to solve these types of cases. In this tutorial we will:

1. Open an existing HydroBID Flood project.
2. Create a scenario for a single pollutant.
3. Create an *Initial Concentrations* layer.
4. Enter pollutant data.
5. Generate the mesh and Export the files to HydroBID Flood.
6. Run the HydroBID Flood model.
7. Review the output files.


The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'SimulatingPollutants' folder. This zip file is downloaded separately from your installation materials. Please refer to the *HydroBID Flood Reference Manual* for additional specifications and requirements to run the *Pollutant Transport* model.

14.1 Create a scenario to model a single pollutant as an initial condition

There are a few layers involved with handling the introduction of pollutants in the areas of interest, depending on the conditions that will be simulated. For this section, we will create a scenario named SinglePollutant that will showcase a an existing pollutant that is already present initially and is part of the discharge of the river. The water body will be utilizing an *Initial Concentrations* layer to have the desired concentration for the same pollutant present.

1. In QGIS, in the *File* menu click *Open*. Browse to the tutorial folder and select the 'Simulating-Pollutants.qgz' project and click [OK].

2. In the HydroBID Flood toolbar click on the New Project button and select *New Scenario*:



New Scenario button location.


3. Type "SinglePollutant" without quotes as your new scenario name. A copy of the current project will be made and kept in a separate subfolder named "SinglePollutant"



New Scenario input dialog window.


14.2 Create an Initial Concentrations layer.

1. In the HydroBID Flood toolbar, click on the dropdown button for *HBF* tools and click *New Template Layer*:




New Template Layer button location.

2. In the *Add Layer Template* dialog window, select the *InitialConcentrationsPollutant* checkbox and click [OK].



Add Layer Template window with InitialConcentrationsPollutant selected.

A new layer should appear in the *Layers* panel on the left-hand side:




Layers panel with InitialConcentrationsPollutant selected.

We need to create a polygon in the *Initial Concentrations* layer that covers all of the river. We can utilize the *Domain Outline* layer and copy the same polygon into our newly created layer.

3. Select the *Domain Outline* layer in the *Layers* panel.

4. Click on the *Select Feature by Area or Single Click*  button, then click inside of the *Domain Outline* polygon in the map area to highlight it:



Map area with Initial Concentrations selected.

5. Click the *Copy Features*  button from the QGIS toolbar.

6. Select the *Initial Concentrations* layer in the *Layers* panel and click on the *Toggle Editing*  button to put the layer in edit mode.

7. Click the *Paste Features*  button.

14.3 Enter pollutant data.

1. Right-click the *InitialConcentrationsPollutant* layer in the *Layers* panel and select *Open Attribute Table*.

2. In the *InitialConcentrationsPollutant* features window, click on the [Browse] button for the *Initial Concen* field.

3. In the project folder, browse into the project folder and select 'InitialConcentration.txt', copy it, then go back to the main project folder and browse to the *SinglePollutant* folder and paste it

there. Click on the file again and click [Open].

4. Close the *InitialConcentrationsPollutant* Features dialog window.

5. Click the *Save Layer Edits*  button then click the *Toggle Editing*  button.

14.4 Generate the mesh and Export to HydroBID Flood

1. Generate the mesh by clicking on the *Generate TriMesh with elevations*  button in the *Generate TriMesh* menu:



Generate Trimesh with Elevations menu location.

Ensure that the “Magdalena” DEM is selected in the *Raster Layer List* dropdown.


2. Export the project to HydroBID Flood by clicking the *Export HydroBID Flood* button in the HydroBID Flood toolbar.

3. You will be presented with the *Export Files to HydroBID Flood* dialog. Leave all parameters as they are and click [OK].



Export Files to HydroBID Flood dialog window.


In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


We want to start the model with a body of water present in the river channel. Since this area is below sea level, we will set a horizontal water surface elevation to provide water below that level in the DIP.

4. The *Hydronia Data Input Program* will open. Under *Modules* select the *Pollutant Transport* radio button. Under *Initial conditions* section, click the *Horizontal water surface elevation* radio button, leaving it at 0 then and click on *Pollutant Transport* on the left side panel:



QGIS DIP Control Data panel for the Single Pollutant scenario.


The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Hydronia Data Input Program dialog window.


5. In the *Name* section double click in the empty cell and write *Pollutant1*, then set the *P1* column value for the row to 0.

   The *Pollutant Transport* panel allows the user to control Dispersion coefficients for all pollutants, as well as define the decay rate for each pollutant. We want to set the decay rate to 0 and leave the rest as default.



QGIS DIP Pollutant Transport panel for the Single Pollutant scenario.

The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Pollutant Transport panel.

6. Click on the [Save .SOLUTES] button, it will use the name of the scenario ‘A.SOLUTES’. Click [OK] to save the file.


14.5 Review Boundary Condition Panel for Pollutant Inflow

The pollutant we have specified will be arriving via the inflow boundary condition that was present in the base tutorial files.

> **Note**
>
> The pollutant concentration units are arbitrary. Your can use volume concentration Cv (fraction of 1), mg/l, ppt, ppm, or any other suitable units, provided that the inflow boundary conditions are consistent.


You can view the boundary conditions file to see the additional column that is required, noting the additional column present in the ‘QIN2.DAT’ file:

1. Click on the *Open Boundary Conditions* panel on the left-hand side.



QGIS DIP Open Boundary Conditions panel for pollutant inflow.

The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Boundary Conditions panel.

2. Switch back to the *Control Data* panel and click [Save .DAT]. Replace the existing 'SinglePollutant.dat' file to save the changes made earlier.

3. Click [Run HydroBID Flood] to execute the model.

14.6 Review the output files


The output maps for pollutants will show us the concentrations over the model domain. We will use the *Concentrations and Properties vs. Time Maps* tool to generate them.

1. In QGIS, Click on the  button and select *Concentrations and Properties vs. Time*


Maps.

2. in the *Concentrations and Properties vs. Time Maps* dialog window, click the [. . .] button and select the 'A.SOLUTES' file and click [OK].

3. Select *Conc_1* under *Maps*, then select the last output time, then click the right arrow button to make the selection. You may also hold the control key and select multiple output times. Click [OK] when ready.



Concentrations and Properties vs Time Maps dialog window.




Output map for Pollutant 1.

14.7 Create a second scenario for adding a new pollutant source under existing conditions

We will now create a new scenario to test having an additional separate pollutant enter the river from a specific point by utilizing a *Sources/Sink* layer.


1. In the HydroBID Flood toolbar click on the New Project button and select *New Scenario*:



New Scenario button location.


2. type “MultiplePollutant” without quotes as your new scenario name. A copy of the current project will be made and kept in a separate subfolder named “MultiplePollutant”

3. In the HydroBID Flood toolbar, click on the dropdown button for *HBF* tools and click *New Template Layer*:



New Template Layer button location.

4. In the *Add Layer Template* dialog window, select the *Source/Sink* checkbox and click [OK].




Add Layer Template window with Sources/Sink selected.


A new *Sources* layer will appear on the lefthand *Layers* panel, under the *COMPONENTS* group.

5. Select the *Sources* layer and click the *Toggle Editing*  button.

We want to place the second pollutant in the middle of the river, ideally somewhere away from our inflow.

6. Click the *Add Point Feature*  .

7. Place the point by clicking on the desired location. A dialog window will appear to enter the source information:



Sources -Feature Attributes General tab.

8. Select *1.Discharge vs Time* under *Source/Sink type*. Click the *Data* tab.

   Your sources file has to exist in the *MultiplePollutant* folder, we must copy the one created for this tutorial into the current scenario folder.

9. Browse by clicking the [Import Source/Sink File] button. Browse to the project base scenario directory at '/SimulatingPollutants/base' and copy the 'Source2_Pollutant.txt' file.

10. Browse back to the current scenario folder in 'SimulatingPollutants/MultiplePollutant'. Paste the copied file into this directory. Select the copied file 'Source2_Pollutant.txt' then click [OK] twice to save the Sources information.

11. Click the *Save Layer Edits*  button then click the *Toggle Editing*  button.

12. Export the project to HydroBID Flood by clicking the *Export HydroBID Flood* button in the HydroBID Flood toolbar. Leave all default values.

14.8 Adding required multiple pollutants concentrations information

This section will explain how to edit inflows and initial concentrations needed in the current Scenario B in order to run the simulation with multiple pollutants.
We need to copy the 'InitialConcentration.txt' file from our project folder into our current scenario:


1. In *File Explorer*, browse to the 'ExampleProjects/SimulatingPollutants/' and copy the 'Initial-Concentration.txt' file.

2. Browse to ‘ExampleProjects/SimulatingPollutants/MultiplePollutant’ and paste the file.

3. Double-click the ‘InitialConcentration.txt’ to edit the contents in Notepad.

   This file needs to contain a second column indicating there is a second pollutant, with 0 concentration. You can set this to be any concentration

4. Add a 0 next to the current one, they can be separated by a space or tab. It should look like this:




InitialConcentrations.txt file with edits.

5. Save the file and close it.

6. In *File Explorer*, double-click on ‘QIN2.txt’ to edit it in Notepad.

7. Add a fourth column of data starting on the second row. We will set the inflow for this pollutant to 0 since we only want one pollutant entering the through the inflow boundary condition:



Boundary Condition inflow file with additional pollutant inflow set to 0.

14.9 Add the new pollutant parameters in the Hydronia Data Input Program then Run the HydroBID Flood model

Before running the model we will need to ensure that some additional settings are saved.


1. In the *Control Data* panel under the *Modules* section, ensure that *Pollutant Transport* is enabled.

2. In the *Components* section, ensure that *Sources/Sinks* is enabled.

3. Under *Initial conditions*, ensure that the *Horizontal water surface elevation* radial button is enabled and has a 0 value, then and click on *Pollutant Transport* on the left side panel.


   We need to add our second pollutant information.

4. Under the *Name* section below *Pollutant1*, then create an additional pollutant by double-clicking in the empty row and set the *P2* column value for the second row to 0. Your *Pollutant Transport* panel should look as follows:



QGIS DIP Pollutant Transport panel with two pollutants.

The following Classic DIP panel is retained as a legacy values reference:




Legacy Classic DIP Pollutant Transport panel with two pollutants set.

5. Click on the [Save .SOLUTES] button, it will use the name of the scenario 'MultiplePollutant.SOLUTES'. Click [OK] to overwrite the existing file.


6. Click on the *Sources and Sinks* button on the left side panel.

7. Click [Open .SOURCES]. Select the 'MultiplePollutant.SOURCES' file. You should see the table for the new pollutant source discharge on the 4th column.



QGIS DIP Sources and Sinks panel for the Multiple Pollutant scenario.


The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Sources and Sinks panel with new pollutant source added.


8. Click on *Control Data* on the left side panel.

The *Control Data* panel should have the following parameters set:



QGIS DIP Control Data panel for the Multiple Pollutant scenario.

The following Classic DIP panel is retained as a legacy values reference:



Legacy Classic DIP Hydronia Data Input Program with Scenario B settings.

9. Click [Run HydroBID Flood]. When asked to save, click [Yes] to overwrite the MultiplePollutant.DAT file with the changes made in the Hydronia Data Input Program.

Once the model is finished running, you can follow the same steps outlined in the *Review output files* section of this tutorial. You will notice there are two concentrations in the list. The output for the new source *Conc_2* should look something like this, depending on where you placed your source:



Figure 14.1 – Concentrations map for Conc_2 in scenario MultiplePollutant.

This concludes the tutorial for simulating pollutant transport with HydroBID Flood.

15 | Wind driven circulation

HydroBID Flood and OilFlow2D allow defining wind velocity on the water surface to account for the effect of the wind stress on the flow velocities. The conceptual model of a wind driven simulation require a series of non-overlapping polygons that determine the wind velocity data to the model. Only areas covered by polygons will be affected by the wind stress. Each wind velocity polygon should be associated with a file containing a wind velocity time-series file containing the two components of the wind velocity vector for each time. The user will need to generate the wind velocity data file associated with each polygon, and copy them to the project folder, prior to running the model.
This tutorial illustrates how to perform a wind drive simulation using the QGIS interface. The procedure includes the following steps:


1. Create time series data for wind speed.
2. Open an existing HydroBID Flood / OilFlow2D project.
3. Create the template of the wind layer and the wind speed polygons.
4. Generate the mesh.
5. Running the model.
6. Review wind output files.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'WindTutorial' folder. This zip file is downloaded separately from your installation materials.

15.1 Open an existing project

1. Open QGIS
2. On the *Project* menu click *Open…* to load the existing project: 'WindTutorial.qgz'.

This project contains the layers of the domain contour and the layer of the Digital Elevation Model (DEM) of Lake Champlain in the USA. When the project is opened, a project image will be loaded in



QGIS as shown in Figure 15.1.

15.2 Wind velocity time-series data file

To run a wind driven simulation you create polygons over which the wind velocity data will be applied. Each polygon will have an associated velocity time series. These files can be created with any text editor such as Notepad or Wordpad. The wind velocity file has the following format:

Line 1: Number of points in the time series of wind velocity

NP

NP lines containing:

TIME Wvx Wvy

where Wvx and Wvy, are the wind velocity components in *x* and *y* directions respectively in m/s or ft/s.

The following table is an excerpt of the 'WindVelocDATA.TXT' file that is included in the Data folder for this tutorial:

6544

0 5.97 −2.17

1	5.09	8.83
2	3.84	6.63
3	5.87	4.92
4	0.00	0.00
5	−3.31	−1.90
...		
6543	3.84	−6.63


15.3 Create the template for the wind layer and the wind speed polygons

To add the template where the polygons are drawn with the wind speed time series data involves the following steps:


1. Create the template for the Winds layer: In the model toolbar click on the *New Template Layer* command



2. In the plugin window, activate the *Wind* checkBox, as shown in the Figure below:



Plugin to add a New Template Layer.



Plugin to add a New Template Layer.

3. Edit the Wind layer: In the layers panel, we select the Wind layer and in the digitization toolbar we click on the *Toggle Editing* tool  . A pencil icon will appear in the Wind layer, indicating that the layer is in edit mode:




4. Draw the polygon that demarcates the Wind area: Using the *Add Feature* tool from the digitization toolbar  .

   Draw the polygon that defines the wind area. In this case, the tracing of the polygon must be done in such a way that it covers all the cells of the mesh. Once you finish drawing the polygon a window to input the polygon parameters is immediately opens, which are three:


   - Wind stress coefficient CD: 0.009,
   - Air density: 1.225, and
   - Wind speed time series File: 'WindVelocDATA.txt'.

   The parameter window should be as shown below:



Window to input the Wind polygon parameters.

5. After input the values, click *OK* and accept the changes. There should be an image similar to the one shown in the following figure:




Wind layer polygon.

15.4 Generate the mesh

Then the mesh is generated with the *Generate TriMesh* button







The results obtained as shown in Figure 15.6 (mesh of around 17,500 cells).

15.5 Exporting files

Now that the mesh is generated and the other layers are ready with the necessary data, export the files in the format required by the model.

1. Uncheck the *Boundary Conditions* layer.
2. Click on the *Export* button






3. In the dialog, select the raster layer that contains the Digital Elevation Model (DEM) and the name of the project to be exported.

4. Use the *Zoom Full* button  to center the image.

5. Before executing the plugin activate the DEM layer (if it is deactivated).

   Once the plugin is executed, a window will be shown (Figure 10.6) as it should be for our example.




Plugin window to export the files to HydroBID Flood.



Plugin window to export the files.

6. Click on the OK button.


   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.



Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


15.6 Running the model

After exporting the files, Hydronia Data Input Program is loaded with the project file from the 'Wind-Tutorial.DAT' example and shows the *Control Data* panel.



1. Enter the information as illustrated in Figure 15.9

   The following Classic DIP panel is retained as a legacy values reference:



2. Verify that the *Wind* component is selected.

3. Select the *Wind* component from list in the left side of the panel. The window with the information of the wind parameters will appear as can be seen in the figure below:




Figure 15.1 – QGIS DIP Wind component panel.

The following Classic DIP panel is retained as a legacy values reference:

![Legacy Classic DIP Hydronia Data Input Program Wind panel.](img/dipwind2.png){ width=100%

4. Verify that the simulation time is set to 24 hours and the output interval is set to 0.5 hours.

5. Verify that the *Initial conditions* is set to *Horizontal water surface elevation* and 0 on the text box. Leave all other parameters at their default values.

6. Click on the *Run HydroBID Flood* button in the lower section of Hydronia Data Input Program.

7. Save the changes with the same name as the 'base.DAT' file, then a window will appear indicating that the model started running.

The model window that appears during the run model shows several runtime parameters.




Figure 15.2 – Model window.

15.7 Check the wind output files

The model creates the following files for each output time as defined in the Control panel:
'CELL_TIME_METRIC_DDDD_HH_MM_SS.TEXTOUT' (Metric Units) or
'CELL_TIME_ENG_DDDD_HH_MM_SS.TEXTOUT' (English Units)
where DDDD indicates the day, HH, hour, MM minutes and SS seconds.
In these files, columns 1, 2 and 3 report the velocity components in Vx, Vy and the module respectively. We can visualize the water velocity fields generating layers either in raster or vectorial format from the aforementioned files using the *Maps of Results vs Time* tool.

The following figure shows the water velocity field map for time 0000:20:00:00:




Figure 15.3 – Map with the speed field for the time 20 hours.

This concludes the *Wind driven circulation* tutorial.

16 | Using Manning's n ESRI shape files

This tutorial illustrates how to use Manning's n files in ESRI shape file format to assign Manning's n values to an existing project using the QGIS interface. The procedure includes the following steps:

1. Open an existing HydroBID Flood project.

2. Load the shape files with the Manning's n polygons.

3. Import the Manning's n geometry and values to the *Manning N* layer.


The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'ManningsNShapefileTutorial' folder. This zip file is downloaded separately from your installation materials.

16.1 Open an existing project

1. Open QGIS

2. On the *Project* menu click *Open…* and browse to the existing project: .

   This project contains the layers of the domain contour, the Digital Elevation Model (DEM) of the river bed in raster format, an aerial photograph, and the boundary conditions layer where the inflow is located in the upper right and outflow in the lower left. The inflow boundary condition is a hydrograph with a peak discharge of 220,000 ft^3/s, and the outflow conditions is set to *Free outflow*. When you open the project you will have an image of the project loaded in QGIS as shown



in 16.1.


16.2 Load the shape file with the Manning's n polygons

1. In order to load the shape file with the polygons containing the Manning's n values, click on *Add Vector Layer* button

   of Manager layer toolbar or from the main menu *Layer* > *Add layer* > *Add Vector Layer…*

2. In tutorial folder under the *base* subfolder, select the 'SaltRiver_ManningsN.shp' file (Figure 16.2).

   When loading the file, an image similar to the one shown in the following figure will be displayed on the screen:



SaltRiver_ManningsN Layer.

16.3 Import the Manning's n geometry and values to the Manning N layer

To transfer spatial and attributive information from the shape file to the *Manning N* layer, a copy and paste operation is performed, but it must be ensured that both layers have a field or column with the same name. The procedure is as follows:

1. Check the field names of the shape file: Right-click on the *SaltRiver_ManningsN* layer label and in the pop-up menu select the option *Open attribute table* (Figure 16.4).


SaltRiver_ManningsN — Features Total: 69, Filtered: 69, Selected:

	LUCode	N_Value
1	Farm_medium	0.06
2	Veg_low	0.04
3	Veg_medium	0.055
4	Veg_medium	0.055
5	Farm_medium	0.06
6	Water	0.03
7	Farm_low	0.05
8	Veg_low	0.04
9	Veg_low	0.04
10	Veg_medium	0.055
11	Veg_medium	0.055
12	Veg_low	0.04
13	Farm_dense	0.085
14	Urban_blocked	0.13
15	Farm_low	0.05

Show All Features

You can see that the shape file loaded has two fields, *LUCode* and *N_Value*, the first one with the coding of the land cover type and the second corresponds to the value of the Manning's n, in the case of the Manning N layer, it has a single field called *ManningN*.


2. Proceed to change the name of the field *N_Value* to *ManningN*. Close the table of attributes and right-click on the layer label. In the pop-up menu, select Properties then in window that opens select the Fields tab as shown in Figure 16.5:



3. Click on the *Toggle Editing* button




then change the *N_Value* field name by *ManningN* (Figure 16.6), and click on the *Toggle Editing* button again, and save.



4. Copy the polygons of the shape file: select the *SaltRiver_ManningsN* layer in the Layers Panel.

5. With the select tool  we draw a rectangle that covers the entire layer:




Selecting all the polygons in the SaltRiver_ManningsN layer.

6. Copy the spatial elements by clicking on the *Copy* button  of the digitization toolbar

7. Paste the spatial elements in the *Manning N* layer: select *Manning N* layer of the Layers Panel and set it in edit mode by clicking on the *Toggle Editing* button  .

8. Click on the *Paste Feature* button  .

   and a message will appear that indicates that features were successfully pasted.

9. Click on the *Toggle Editing* button again  .

   Confirm and save the changes made to the layer.

To verify the operation was successful, open the attribute table of the *Manning N* layer and you can see that the polygons have been copied with their Manning n values. As shown in the Figure below:




Figure 16.1 – Attribute table of the Manning N layer.

You can now remove the *SaltRiver_ManningsN* layer from the Layer Panel.
This concludes the *Using Manning's n ESRI shape files* tutorial.

17 | Post-processing calculations

HydroBID Flood has three output controls that make it easier for the user to analyze the results of the runs at specific sites in the domain calculator. These output controls are: Observation points, Cross sections and Profiles.

This tutorial illustrates how to incorporate the output controls in a model using the QGIS interface. The procedure includes the following steps:


1. Open an existing HydroBID Flood project.
2. Create *ObservationPoints*, *CrossSections* and *Profiles* layers, and draw the output controls.
3. Generate the mesh.
4. Running the model.
5. Review output files.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'OutControlTutorial' folder. This zip file is downloaded separately from your installation materials.

17.1 Open an existing project

1. Open QGIS
2. On the *Project* menu click *Open…* and browse to the existing project: 'OutControlTutorial.qgz'.

   This project contains the layers of the domain outline, the Digital Elevation Model DEM of the river bed in raster format, the layer with the boundary conditions where inflow is located in the upper left and outflow in the lower left. The boundary conditions are a hydrograph with a peak discharge of 6,500 ft^3/s and outflow condition set to *Free outflow*. When you open the project you will have an image of the project loaded in QGIS as shown in Figure 17.1.



17.2 Create a template of the layers *ObservationPoints*, *CrossSections* and *Profiles* and draw the output controls


To add the templates where the different output controls are drawn involves the following steps:

1. Create the templates of the layers *ObservationPoints*, *CrossSections* and *Profiles*: for this in the HydroBID Flood toolbar click on the *New Template Layer* button






2. In the plugin window activate the checkBox *ObservationPoints*, *CrossSections* and *Profiles*, as shown in the Figure below:



Plugin to add the new templates layer.




Plugin to add the new templates layer.

3. Edit the layers and draw the output controls: Select in the layers panel, the *ObservationPoints*, *CrossSections* and *Profiles* layers one by one.

4. Click on the *Toggle Editing* button:



A pencil will appear on the label of the layers, indicating that the layers are in edit mode:



5. Draw the lines or points that represent the output control: To draw the cross sections, profiles or observation points, the *Add Feature* tool will be used.

   for the *CrossSections* and *Profiles* layers, the icon for the *Add Feature* button is


   

   in the case of a point layer like *ObservationPoints*, the icon is


   


6. Drawing the cross sections: Select the *CrossSection* layer, and activate the *Add Feature* button.

7. Proceed to draw three sections: One at the beginning of the channel, another in the middle and the third almost at the end of the channel, identify (XSECID) as: Section1, Section2 and Section3, with intervals (ND_CS) of 10, 15 and 20 respectively. The attribute tables of the sections will be as shown in Figure 17.4 and at the end of the drawing a similar image should


   


   appear as shown in the following Figure 17.5.



8. Save the polygon by clicking the Save button  and click on the *Toggle Editing* button  to deactivate Edit mode on the CrossSections layer.


9. Drawing the Profile: Select the Profile layer and activate the Add Feature button, we proceed to draw the profile along the channel central axis, identifier (PROFILEID) is Profile1 and the number of intervals (ND_PR) equal to 50. The attribute table will be as shown in Figure 17.6. Once finished drawing, it should appear like the one shown in the following Figure 17.7.





10. To finalize the profile drawing, save the polygon by clicking the Save button  and click on *Toggle Editing* button  to deactivate Edit mode on the Profile layer.

11. Drawing the observation points: Select the *ObservationPoints* layer, and activate the *Add Feature* button, proceed to draw two observation points, the first between sections 1 and 2 and the second between sections 2 and 3. The identifier (ObsID) is assigned as Point1 and Point2, respectively. The attribute tables will be as shown in Figure 17.8 and at the end of the drawing you should have an image similar to the one shown in the following Figure 17.9.




12. To finish the drawing of the observation points, you click again on the *Toggle Editing* button to disable the editing mode of the *ObservationPoints* layer.

17.3 Generate the mesh

The mesh is generated with the *Generate TriMesh* button







The result is a mesh of approximately 9,000 cells, as shown in Figure 17.10.

17.3.1 Exporting files to HydroBID Flood

Now that the mesh is generated and the other layers are ready with the necessary data, export the files in the format required by HydroBID Flood.


1. Click on the *Export HydroBID Flood* button



2. When run the plugin a window is displayed, select the raster layer that contains the Digital Elevation Model (DEM) and the name of the project to be exported.

3. Before executing the plugin, activate the layer with the DEM (if it is deactivated).

   After running the plugin, a window will be shown (Figura 17.11), como debe ser para nuestro ejemplo.






Plugin to export the files to HydroBID Flood.

4. Once finished inputting the information, click the [OK] button to export the files to the model.

   In Hydronia2DMS version 10 and later, the *Open DIP* dialog appears after export. *QGIS DIP* is selected by default; click *OK* to open it inside QGIS. To view the historical standalone alternative, expand *More options*, select *Classic DIP*, and then click *OK*.




Open DIP dialog showing QGIS DIP selected by default and More options expanded with Classic DIP. Example run name shown.


Once it is finished, HydroBID Flood will be loaded with the 'base.DAT' file.

17.4 Running the Model

After exporting the files, HydroBID Flood opens with the project file of the 'OutControl.DAT' sample and shows the *Control Data* panel to it as illustrated in Figure 17.13.




The following Classic DIP panel is retained as a legacy values reference:



You can observe in the control panel in Output Options the outputs of results for *Cross Sections*, *Profiles* and *Observation Points* are selected.

Leave all other parameters at their default values.

To run the model, click on the *Run HydroBID Flood* button. The window that HydroBID Flood presents while running the model shows: simulation time information, volume conservation error, total discharge of inflow in and outflow, as well as other parameters as execution progresses (Figure 17.14).



17.5 Review the output files

HydroBID Flood generates the files with the extensions '.xseci' (metric units) and '.xsece' (English units) which report the results along the cross sections. it generates files with extensions '.prfi' (metric units) and '.prfe' (English units) which report the results along the profiles and generates the

files with the extensions '.outi' (metric units) and '.oute' (English units) that report the results in the observation points.

Figure 17.15 shows an extract of the 'OutControl.xsece' file with results at the cross sections:

```
================================================================================
================================================================================
                          RiverFlow2D
                          Build Mar  9 2023
================================================================================
             TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
                       (R) TRADEMARK 2009-2022 Hydronia, LLC.
                                   ALL RIGHTS RESERVED
                                   RUN DATE: 27/Mar/2023
================================================================================

 CROSS SECTION RESULTS IN ENGLISH UNITS

 TIME: 0000 days, 00 hours, 00 min.,00 secs.


 CROSS SECTION NO.:   1 CROSS SECTION ID: XSEC_1

 (     243444.89,       94253.80), (     243571.18,       94402.64)
 ELEM    STATION    BEDEL     DEPTH     WSEL     VELOCITY  FROUDE     QS
          (ft)      (ft)      (ft)      (ft)      (ft/s)           (ft2/s)
  6351     13.80     50.16      0.00     50.16      0.00      0.00  0.000000
   587     23.66     49.49      0.00     49.49      0.00      0.00  0.000000
   359     35.49     49.52      0.00     49.52      0.00      0.00  0.000000
  2325     41.41     49.33      0.00     49.33      0.00      0.00  0.000000
  1551     57.18     49.22      0.00     49.22      0.00      0.00  0.000000
   293     67.04     49.10      0.00     49.10      0.00      0.00  0.000000
  6321     72.95     48.87      0.00     48.87      0.00      0.00  0.000000
  4106     80.84     48.82      0.00     48.82      0.00      0.00  0.000000
  1836     90.70     48.70      0.00     48.70      0.00      0.00  0.000000
  1597     94.64     49.04      0.00     49.04      0.00      0.00  0.000000
  3138    102.53     49.23      0.00     49.23      0.00      0.00  0.000000
   809    106.47     49.85      0.00     49.85      0.00      0.00  0.000000
    95    110.42     50.70      0.00     50.70      0.00      0.00  0.000000
  4592    124.22     51.52      0.00     51.52      0.00      0.00  0.000000
  2008    130.13     51.58      0.00     51.58      0.00      0.00  0.000000
  6910    139.99     51.70      0.00     51.70      0.00      0.00  0.000000
  1814    143.94     51.98      0.00     51.98      0.00      0.00  0.000000
  1411    149.85     52.02      0.00     52.02      0.00      0.00  0.000000
  2062    159.71     52.13      0.00     52.13      0.00      0.00  0.000000
   356    165.62     52.07      0.00     52.07      0.00      0.00  0.000000
  3167    175.48     52.21      0.00     52.21      0.00      0.00  0.000000
  6739    185.34     52.39      0.00     52.39      0.00      0.00  0.000000
 Q =     -0.000 cfs.


 CROSS SECTION NO.:   2 CROSS SECTION ID: XSEC_2

 (     243995.16,       93802.76), (     243602.76,       93800.51)
 ELEM    STATION    BEDEL     DEPTH     WSEL     VELOCITY  FROUDE     QS
          (ft)      (ft)      (ft)      (ft)      (ft/s)           (ft2/s)
  7097     19.82     54.90      0.00     54.90      0.00      0.00  0.000000
  6346     23.78     54.22      0.00     54.22      0.00      0.00  0.000000
  6157     27.75     51.32      0.00     51.32      0.00      0.00  0.000000
   121     35.67     48.75      0.00     48.75      0.00      0.00  0.000000
   184     39.64     46.82      0.00     46.82      0.00      0.00  0.000000
  2632     47.56     46.00      0.00     46.00      0.00      0.00  0.000000
  2968     51.53     45.98      0.00     45.98      0.00      0.00  0.000000
  4400     55.49     46.02      0.00     46.02      0.00      0.00  0.000000
   682     59.46     46.51      0.00     46.51      0.00      0.00  0.000000
```

Figure 17.16 shows an extract of the 'OutControl.prfe' file with the report of the profile results:

```
================================================================================
================================================================================
                          RiverFlow2D
                          Build Mar  9 2023
================================================================================
             TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
                       (R) TRADEMARK 2009-2022 Hydronia, LLC.
                                   ALL RIGHTS RESERVED
                                   RUN DATE: 27/Mar/2023
================================================================================

 PROFILE RESULTS IN ENGLISH UNITS

 TIME: 0000 days,00 hours,00 min.,00 secs.

 PROFILE NO.:   1 PROFILE ID: PROFILE_1

 ELEM   DISTANCE    BEDEL     DEPTH      WSEL    VELOCITY  FROUDE
          (ft)      (ft)       (ft)      (ft)     (ft/s)
  6406      0.00     48.55     15.61     64.17      0.00      0.00
  4446     15.34     48.69      0.00     48.69      0.00      0.00
  3736     30.68     48.61      0.00     48.61      0.00      0.00
  1927     46.02     48.56      0.00     48.56      0.00      0.00
  2357     61.36     48.76      0.00     48.76      0.00      0.00
  1836     76.69     48.70      0.00     48.70      0.00      0.00
  8006     92.03     48.82      0.00     48.82      0.00      0.00
  6142    107.37     48.81      0.00     48.81      0.00      0.00
    80    122.71     48.78      0.00     48.78      0.00      0.00
  1878    138.05     48.69      0.00     48.69      0.00      0.00
  1622    153.39     48.63      0.00     48.63      0.00      0.00
   978    168.73     48.65      0.00     48.65      0.00      0.00
  6342    184.07     48.71      0.00     48.71      0.00      0.00
  5985    199.41     48.76      0.00     48.76      0.00      0.00
   843    214.74     48.78      0.00     48.78      0.00      0.00
  6360    230.08     48.89      0.00     48.89      0.00      0.00
   575    245.42     48.92      0.00     48.92      0.00      0.00
  4957    260.76     49.01      0.00     49.01      0.00      0.00
  4201    276.10     49.02      0.00     49.02      0.00      0.00
  2430    291.76     48.84      0.00     48.84      0.00      0.00
   734    307.41     48.79      0.00     48.79      0.00      0.00
  3495    323.07     48.91      0.00     48.91      0.00      0.00
  6854    338.72     49.05      0.00     49.05      0.00      0.00
  6256    354.38     49.03      0.00     49.03      0.00      0.00
  3401    370.03     48.65      0.00     48.65      0.00      0.00
  3600    385.69     48.45      0.00     48.45      0.00      0.00
  5619    401.34     48.52      0.00     48.52      0.00      0.00
  3586    417.00     48.77      0.00     48.77      0.00      0.00
   822    432.66     48.39      0.00     48.39      0.00      0.00
  4197    448.31     48.17      0.00     48.17      0.00      0.00
  5100    463.97     48.00      0.00     48.00      0.00      0.00
   194    479.62     47.93      0.00     47.93      0.00      0.00
  3785    495.28     47.54      0.00     47.54      0.00      0.00
  4267    510.93     46.81      0.00     46.81      0.00      0.00
  7358    526.59     46.52      0.00     46.52      0.00      0.00
  2123    540.71     46.84      0.00     46.84      0.00      0.00
  8723    554.84     46.76      0.00     46.76      0.00      0.00
  4474    568.96     47.17      0.00     47.17      0.00      0.00
  5572    583.08     45.98      0.00     45.98      0.00      0.00
  6970    597.21     46.20      0.00     46.20      0.00      0.00
  2493    611.33     46.19      0.00     46.19      0.00      0.00
```

Figure 17.17 shows an extract of the 'RESvsT_Point1.oute' file with the report of the results of the ob-

```
================================================================================
================================================================================
                          RiverFlow2D
                          Build Mar  9 2023
================================================================================
            TWO-DIMENSIONAL FINITE VOLUME RIVER DYNAMICS MODEL
                      (R) TRADEMARK 2009-2022 Hydronia, LLC.
                                  ALL RIGHTS RESERVED
                                  RUN DATE: 27/Mar/2023
================================================================================

 RESULTS FOR CELL:      840 OBSERVATION POINT ID: Point2
   LOCATED AT COORDINATE: (   243832.78),(    93473.50)

      TIME         U         V     VELOCITY    DEPTH      WSEL    BEDEL_ORI   BEDEL    DELTA_BED  FROUDE     QSX          QSY          QS
     (hours)    (ft/s)    (ft/s)    (ft/s)      (ft)      (ft)       (ft)      (ft)       (ft)      (-)     (ft2/s)      (ft2/s)      (ft2/s)
     0.10000    -2.897    -7.137     7.703     4.806    52.126     47.319    47.319     0.000     0.619     0.000      0.000     0.000
     0.20000    -2.736    -6.929     7.450     5.019    52.338     47.319    47.319     0.000     0.586     0.000      0.000     0.000
     0.30000    -2.720    -6.901     7.418     5.035    52.355     47.319    47.319     0.000     0.583     0.000      0.000     0.000
     0.40000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     0.50000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     0.60000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     0.70000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     0.80000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     0.90000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.00000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.10000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.20000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.30000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.40000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.50000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.60000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.70000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.80000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     1.90000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
     2.00000    -2.718    -6.898     7.414     5.038    52.357     47.319    47.319     0.000     0.582     0.000      0.000     0.000
```

servation point Point1:

18 | Advanced digitization/snapping

In many cases the drawing of polygons that share borders (contiguous) is required. Trying to do this manually usually produces polygon overlap errors, or it may generate gaps as illustrated in the following figure:




Figure 18.1 – Areas with overlap and empty spaces in manual digitization of adjacent polygons.

This tutorial illustrates how to use the QGIS Snapping tool to facilitate the scanning of adjacent polygons. The procedure includes the following steps:

1. Open an existing HydroBID Flood project.
2. Activate the *Snapping* tool.
3. Configure the *Snapping* tool
4. Draw contiguous or adjacent polygons using the *Snapping* tool.

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'SnappingTutorial' folder. This zip file is downloaded separately from your installation materials.

18.1 Open an existing project

1. Open QGIS

2. In the main menu go to *Project* > *Open…* and browse to the existing project: 'SnappingTutorial.qgz'.

This project contains the basic templates of a HydroBID Flood project and a raster with 4 areas with different Manning's n coefficients derived from land cover and land use maps. From this raster, the polygons of the *Manning N* layer will be drawn. When the project is opened, a project image will be loaded in QGIS as shown in Figure 18.2.





Figure 18.2 – Project screen loaded in QGIS.

18.2 Activate and configure the Snapping tool

To use the Snapping tool, you must activate it beforehand:

1. Open the configuration options window: In the Project menu, select *Snapping Options…*



Project Snapping Settings window.

2. In the *Project Snapping Settings* window, click on the *Enable Snapping* button.



3. Next to the *Enable Snapping* button the dropdown menu for *All Layers* is activated. Click on the dropdown and select *Advanced Configuration*.

4. In the list of layers, make sure only *Manning N* layer is selected.

5. Select the checkbox to *Avoid Overlap* on the *Manning N* layer.

The configuration window of the Snapping tool should be as shown in the following Figure:




Figure 18.3 – Snapping configuration panel.

18.3 Draw contiguous or adjacent polygons using the Snapping tool


To draw the polygons with the information of the Manning's n coefficients we proceed as follows:

1. Edit the *Manning N* layer: In the layers panel, select the *Manning N* layer

2. In the digitization toolbar click on the *Toggle Editing* button




A pencil icon will appear in the *Manning N* layer indicating that the layer is in edit mode:



3. Draw the polygon that demarcates the Manning's n area: Using the *Add Toggle Editing* button in the digitization toolbar




proceed to draw the polygons. Start by drawing the polygon in the bottom of the watershed shown in gray which corresponds to n = 0.02. After completing the drawing you should have an image similar to the one shown in the following figure:



The first polygon sketch.


4. Proceed to draw the second polygon. This will be the small yellow polygon to which corresponds to n = 0.30. To draw the polygon, follow the boundary with the green polygon as indicated by the raster, but in the boundary with the polygon already drawn (the gray) an overlap will be made so that the snapping tool takes the edge that already exists and completes the polygon. Try to make a path as shown in the figure below:



Drawn of the second polygon.


5. Right-click to finish the drawing.

6. Enter the Manning coefficient, n = 0.30 and you will have an image like the one shown below where you can see how the final drawing of the second polygon took the vertices of the first adjacent polygon:




Final draw of the second polygon.

7. The third polygon to be drawn will be the large yellow polygon. Just as in the previous case, the contour of the polygon according to the raster is faithfully followed, but in the adjacent polygons it is already drawn overlapped. The figure below shows the initial drawing, with an approach in the area where the overlap is made with the existing polygon:




Preliminary draw of the third polygon.

8. After finishing the drawing and assigning the *Manning N* umber to the polygon, the final drawing of the third polygon will be shown as shown below:




Final draw of the third polygon.

9. The fourth polygon to draw will be the green polygon which corresponds to n = 0.45. To do it will follow the outer boundary of the same and the boundary with the brown polygon. Then a thick overlap will be made within the polygon already drawn, the yellows and the gray, as shown in the figure below:




Preliminary draw of the fourth polygon.

10. After finishing the drawing and assigning the Manning's n value to the polygon, you will have the final layout of the third polygon as shown below:




Final draw of the fourth polygon.

11. To finish, draw the fifth polygon of brown color, which corresponds to n = 0.03. For this the outer limit is drawn following the contour of the raster and for the shared limits an overlap is made inside the neighboring polygons as shown in the figure below:



Preliminary draw of the fifth polygon.

12. After finishing the drawing and inputting the Manning coefficient to the polygon, you will have the final drawing of the third polygon as shown below:




Final draw of the fifth polygon.

13. To finish, click on the *Toggle Editing* button



changes are accepted and saved. Then the layer of the raster Manning_Map_n is deactivated, and the *Manning N* vectorized layer can be observed as shown in the Figure below:



Final draw of the Manning N layer.

18.4 Delete a polygon

Suppose you want to delete the last polygon created because you are not satisfied with the result. In that case you can proceed doing as follows:


1. The *Manning N* layer is edited using the *Toggle Editing* button



2. Then the polygon to be eliminated is selected using the *Select Feature* button




3. With the active select Feature tool, click on the polygon to be deleted and it will be highlighted in yellow to indicate that it is selected (Figure 18.15).



Polygon to be deleted selected.

4. Then the polygon is deleted either with the Delete key on the keyboard or with the *Delete selected* button





Manning N layer with the polygon removed.

5. Finally, the changes are saved and the editing mode of the layer is deactivated by clicking on the *Toggle Editing* button.



This concludes the Snapping tutorial.

19 | Creating raster elevations from X Y Z data sets

The files required to follow this tutorial can be extracted from the 'ExampleProjects' zip file under the 'InterpolatingRasterTutorial' folder. This zip file is downloaded separately from your installation materials.

HydroBID Flood uses elevation data in raster format. For instance, to load an ASCII grid file, from the *Layer* menu, click *Add Layer*, and then click *Add Raster Layer…* You may also click the *Add Raster Layer* button:



In this example we will use elevation data available in a tab delimited X Y Z file, and create an interpolated raster layer.

The X Y Z file can be formatted as comma, space or tab delimited data, where the first two columns correspond to point X and Y coordinates and the third column is the point elevation Z as shown in the following figure.




Figure 19.1 – File containing terrain elevation points.

First, the X Y Z file is loaded to create an event layer. This can be accomplished as follows:

1. From the *Layer* menu, click *Add Layer*, and then click *Add Delimited Text Layer…* Alternatively, you may also click the *Add Delimited Text Layer* button:



2. Open the elevations file: Click the Browse […] button and go to

   '\ExampleProjects\InterpolatingRasterTutorial\base\HohDTM_points_xyz.txt'.


3. Under *File format*, *Comma Separated Values* should be selected.

4. Under *Record and Fields Options* the checkboxes *First row contains field names* should be selected.

5. Under *Geometry Definition*, click on the *Z field* dropdown and select *z*.


6. The *Geometry CRS* dropdown should be set to *Project CRS: EPSG:2229*.

   The dialog should look like the following figure:




   Dialog to create a layer from delimited data text file.

7. To go to the area where the points are located, you will have to right-click on the label of the created layer and select the option Zoom to the layer.




How to zoom a layer.

8. The points should appear in the project window:




Layer of points created from delimited data file.

9. The raster is created interpolating from the data in the point layer. For that we will use the *Processing Toolbox* to load the panel that will allow us to search for the *TIN interpolation* command.



Opening the Processing Toolbox.



Loading to the QGIS TIN interpolation tool.

10. In this window select the layer to be interpolated to create the raster, in this example we use the point layer that we just created named *HohDTM_points_METRIC*. Change it by selecting the dropdown for *Vector layer*.

11. We select the field that has the attribute that was used as the value to interpolate, in this case the z field. This is done by clicking the dropdown for *Interpolation Attribute*, and select *z*.


12. Click the green + button to add the vector layer into the list.

13. Click on the *Set to current map canvas extent* button and it shoudl automatically fill in the extent information.

14. In the *Pixel size* textboxes, enter *10*. You will notice the *Rows* and *Columns* textboxes are automatically filled in based on the pixel size.

15. Select the path to the folder where the raster layer is to be created. It is recommended to point to the project folder directory chosen earlier in the tutorial.


    The panel should look like the following figure:



Interpolation plugin window.

16. Click OK to start the interpolation process.

Once the process is completed, the raster resulting from the interpolation will be displayed on the



screen, by default it is rendered in gray gradient as shown in Figure 19.8.

Note: Right-clicking on the label of the created layer and selecting *Properties* allows you to change the rendering style for a more informative color palette.




Figure 19.2 – Window to change the render style of a raster layer.

And now the raster layer is displayed with the new color palette selected:




Figure 19.3 – Digital elevation model with color render.

It is convenient to move the raster layer created to the end of the list of layers, thus it does not interfere with the display of other layers.

This concludes the Interpolating Raster tutorial.

20 | Setting up a Google Cloud VM for GPU-Accelerated Simulations

This tutorial provides a step-by-step guide for setting up a powerful virtual machine (VM) on Google Cloud Platform (GCP) equipped with an NVIDIA Tesla V100 GPU. Such a setup is ideal for running computationally intensive HydroBID Flood or OilFlow2D simulations that can leverage GPU acceleration, significantly reducing model run times.

Note: Running a VM with a GPU on Google Cloud will incur costs. Windows Server images and GPUs are premium resources. Please review GCP pricing and ensure billing is enabled for your project. The Google Cloud Free Trial does not typically cover GPU usage. See the official documentation for more details: https://cloud.google.com/compute/docs/create-windows-server-vm-instance.

The process involves these main steps:

1. Configure and create a new Compute Engine VM instance.
2. Specify the machine type (4 vCPUs and 32 GB Memory).
3. Add and configure an NVIDIA Tesla V100 GPU.
4. Select a Windows Server boot disk.
5. Connect to the newly created VM.

20.1 Before you begin

1. You must have a Google Cloud account with a project created and billing enabled.
2. Ensure your account has the necessary IAM permissions. At a minimum, you will need the 'Compute Instance Admin (v1)' and 'Service Account User' roles for the project.
3. Enable the Compute Engine API for your project. This can be done from the APIs & Services dashboard in the Google Cloud Console.
4. You will need an RDP client on your local machine to connect to the Windows VM. Microsoft's Remote Desktop client is available for Windows, macOS, iOS, and Android.

20.1.1 Checking and Requesting GPU Quotas

By default, Google Cloud projects have a GPU quota of zero for most regions to prevent accidental usage. Before you can create a VM with a GPU, you must request and be granted a quota for the specific type of GPU (e.g., NVIDIA Tesla V100) in your desired region.

1. In the Google Cloud Console, navigate to **IAM & Admin** > **Quotas**.
2. In the **Filter** bar, select the **Metric** property and search for NVIDIA V100 GPUs. Select it from the list. If it does not appear, you may need to clear the filter and first filter by **Service** for Compute Engine API.
3. This view will show your current GPU quota for all regions. Most will likely be at 0.
4. Find the region where you plan to create your VM (e.g., 'us-central1') and select the checkbox next to it.
5. Click the **EDIT QUOTAS** button at the top of the page.
6. A panel will open on the right. Enter your desired new quota limit (e.g., 1 for one V100 GPU) and provide a brief justification for your request (e.g., "Required for running GPU-accelerated scientific modeling software").
7. Submit the request. Quota increase requests can take some time to be reviewed and approved by Google. You will receive an email notification once the process is complete. **You cannot proceed with creating the VM until your quota request is approved.**

20.2 Creating the VM Instance

1. In the Google Cloud Console, navigate to the **Compute Engine** service and select **VM instances**.
2. Click the **CREATE INSTANCE** button at the top of the page. This will open the instance creation form.
3. **Name your instance**: Enter a descriptive name, for example, 'hydronia-gpu-workstation'.
4. **Region and Zone**: Select a region (e.g., 'us-central1'). For the **Zone**, select **Any (recommended)**. This allows Google to pick an available zone, which is necessary to trigger the quota request workflow if your quota is insufficient.

20.3 Configuring Machine and GPU

This is the most critical step, where you define the computational resources for your VM. The following steps correspond to the selections shown in Figure 20.1.

1. In the main **Machine configuration** section, first click the **GPUs** button. This filters the available options to those that support graphics processors.

2. A new **Graphics processing units** subsection will appear. Configure it as follows:

    - **GPU type**: Select **NVIDIA V100**.
    - **Number of GPUs**: Select **1**.
    - Leave the **Enable Virtual Workstation (NVIDIA GRID)** checkbox *unchecked*.

3. Next, configure the CPU and memory for the VM itself:

    - **Series**: Ensure **N1** is selected.
    - **Machine type**: Click the **Custom** button.
    - **Cores**: Drag the slider or type **4** into the vCPU box.
    - **Memory**: Drag the slider or type **32** into the GB box. Ensure the **Extend Memory** checkbox is active.





Figure 20.1 – Configuring the machine with a custom N1 type, 4 vCPUs, 32 GB of memory, and one NVIDIA V100 GPU.

20.4 Configuring the Boot Disk and Firewall

1. In the **OS and Storage** section, click the **Change** button.
2. In the fly-out menu, make the following selections:
    - **Operating system**: Select **Windows Server**.
    - **Version**: Select **Windows Server 2019 Datacenter** or a newer version if available.
    - **Boot disk type**: Select **SSD persistent disk** for better performance.
    - **Size (GB)**: Set a size appropriate for your needs, for example, **150** GB.

3. Click **Select** to confirm the boot disk configuration.



Configuring the Windows Server 2019 boot disk.


4. In the **Firewall** section of the main creation page, check both **Allow HTTP traffic** and **Allow HTTPS traffic**. RDP access is enabled by default for Windows instances.

20.5 Create the VM and Handle Quota Requests

1. Review all the settings one last time. At the right side of the page, you will see a monthly cost estimate.

2. Click the **Create** button.

3. If this is your first time creating a GPU-enabled VM, the creation will likely fail with a “VM creation error” pop-up, as shown in Figure 20.3. This is expected and is the easiest way to request the needed quota.




VM creation error due to GPU quota.


4. Click the **Request Quota** button directly within the error dialog.

5. This will open the “Quota changes” request form. You will proceed in two steps:

   - **Step 1/2: Edit Quota** (Figure 20.4)
     - In the New value box, enter 1.
     - In the Request description box, provide a brief justification, such as “Software requires GPU to run for scientific modeling.”
     - Click Done, then click Next.
   - **Step 2/2: Contact Details** (Figure 20.5)
     - Fill in your contact information.
     - Click Submit request.



Requesting a quota increase.




Providing contact details for the quota request.

6. The quota request will be sent to Google for approval. This can take anywhere from a few minutes to a few business days. You will receive an email once the request has been approved. **You must wait for the quota approval before you can successfully create the VM.** Once approved, return to the **VM instances** page in the Google Cloud Console.

7. You will see your failed instance with a red error icon. On the far right of the instance row, click

the wrench icon to **Edit and retry** (Figure 20.6).



Using the Edit and retry option on a failed VM instance.

8. This will take you back to the instance creation page with all of your previous settings pre-filled. Scroll to the bottom and click **Create**. The VM should now be provisioned successfully.

20.6 Connect to the VM

Once your quota request is approved and the VM has been successfully created (indicated by a green checkmark icon on the **VM instances** page), you can set your password and connect.

1. Click on the name of your new VM instance to go to its details page.
2. Under the **Remote access** section, click the **SET WINDOWS PASSWORD** button.
3. A default username (your Google account username) will be shown. You can keep it or change it. Click **SET**. A new password will be generated. **Copy this password and store it securely**.
4. You can now connect to your VM. Return to the VM instance details page, click the **RDP** button, and choose **Download the RDP file**. Open this file with your RDP client.
5. When prompted, enter the username and the password you just copied. You are now connected to your new Windows Server VM with a powerful GPU, ready for your simulation work.

This concludes the Google Cloud VM Setup tutorial.

21 | Creating high-impact graphics and animations using Paraview

ParaView is an open-source, multi-platform data analysis and visualization application. You can quickly build visualizations to analyze model results using qualitative and quantitative techniques. The data exploration can be done interactively in 2D and 3D, or using ParaView's batch processing capabilities.

This tutorial will demonstrate the use of Parview to generate high quality graphics, including depth maps, velocity fields, 3D visualizations, and animations of HydroBID Flood results.

> **Note**
> This tutorial requires ParaView version 5.8.1 or later. You can download and install ParaView version 5.8.1 or later from the website www.paraview.org. To create the ParaView graphs, the HydroBID Flood model needs to generate during runtime the '.vtk' files using the *Create graphic output files* option in the Hydronia Data Input Program *Graphic Output Options* panel.

21.1 Paraview basics

After loading Paraview, the following components can be identified in the main window (see Figure 21.1):




Figure 21.1 – Main Paraview window.

To open the tutorial example group file, click  in the Menu bar and double-click the file group 'BridgeTutorial..vtk' in the 'ParavirewTutorial' folder. The group contains multiple '.vtk' files, where each file corresponds to a specific simulation time.

Make it visible clicking *Apply* in the *Properties* tab. The following graphic in the *Render View layout* will look as follows:




Figure 21.2 – View after opening the 'BridgeTutorial..vtk' file.

Using the Time control toolbar (see Figure 21.3), select a time to visualize the selected variable.



Figure 21.3 – VCR and Time Control toolbars.

The graphic will change according with the selected simulation time. For example, for *Time = 2* it should look similar to this:




Figure 21.4 – View for Time = 2.

An adequate visualization depends on the selection of a color scale of a defined variable. In the previous figure, the default color scale was selected associated with the depth variable (h). The next section shows how to customize color rendering.

21.2 Two-dimensional (2D) visualizations

21.2.1 Create a 2D bed elevation map

Paraview has many filters for full visualization of 1D, 2D and 3D data. In this part of the tutorial we will create a 2D bed elevation graphic. Select the bed elevation variable z in the *Variable selector*:




Figure 21.5 – Variable selector.

The representation of the bed elevation z will look like this:




Figure 21.6 – Bed elevation z representation.

Although it is possible to customize the color maps, we will see how to do it later in this tutorial, for this example we will use a predefined color.

Click  in the *Properties* tab to pick up the Rainbow Desaturated color map in the *Choose Preset* dialog box. Once selected, *Apply/Close*.




Figure 21.7 – Predefined color maps.

The result graph visualizes of the bed elevation z.




Figure 21.8 – Bed elevation z representation.

21.2.2 Creating 2D velocity vector fields

In order to create a 2D visualization of the flow and its magnitude with our project data, we will start with a water depth h representation in a white-to-blue color scale. The first step is to select h in the *Variable selector*. To change the color map for water depth h to a white-to-blue, click  and choose the *XRay* preset color then *Apply/Close*. The *Mapping Data* should look as:




Figure 21.9 – XRay Color Map.

Double click in the right circle of the range marker bar and select any blue color from the *Select Color* dialog box. This example uses *Red = 0*, *Green = 85* and *Blue = 255* and Click *OK*




Figure 21.10 – White-to-blue color map.

The *Mapping Data* will look as follows:




Figure 21.11 – White-to-blue color map.

Set the *Time = 20* and the result should look as follows:




Figure 21.12 – Water depth (h).

To create a 2D velocity vector map for this example, follow these steps:

- Select *BridgeTutorial** in the *Pipelines Browser*
- In the *Filters* menu select *Common/Glyph*
- Click *Apply* in the *Properties* panel. You will adjust the big arrows after
- Configure the Vector field configuration in the *Properties* panel as follows:

  - Glyph type: *2D Glyph*
  - Scale Array: modU (velocity modulus)
  - Scale Factor: 35
  - Glyph mode: *Every Nth Point*
  - Click *Apply* to visualize the the filter setup. The user can press this button each time changes are made
  - Coloring: modU

- Choose the Rainbow Desaturated color scale clicking in  and *Apply/Close*.




Figure 21.13 – Velocity vector field on water depth.




Figure 21.14 – Velocity vector field detail.

In order to save the Paraview project, select *File/Save State*. This will save a '.pvsm' file.

21.3 Three-dimensional (3D) visualizations

In this part of the tutorial we will explain the steps to create a 3D visualization using Paraview. We start where section 21.2 ends. This assumes that we have a visualization of the bed elevation (z) variable using the *Rainbow Desaturated* color map.

Open the 'BridgeTutorial..vtk' group as explained in section 21.1 and select the bed elevation variable z in the *Variable selector*. The render view should look as the following figure:





Figure 21.15 – Bed elevation z.


Generating a 3D visualization in ParaView requires an interpolation from *Cell Data to Node Data* as follows.

- Select *Cell Data to Point Data* in the *Filters/Alphabetical* menu. Then, press the *Apply* button in the *Properties* tab.



Cell Data to Point Data filter.

- Select again z in the *Variable selector*. Note that the color view is smoother due to the interpolation. The result should look as follows:



Cell Data to Point Data interpolation.

The 3D appearance is obtained by extruding one of the data variables z or (h+z).

- With the *CellDatatoPoint* selected in the *Pipeline Browser*, select *Warp by Scalar* in the *Filters/Alphabetical* menu to do the extrusion and then click *Apply*.


- Configure the *Properties* tab as follows:

  - Scalars = z

  - Scale Factor = 25


- Click *Apply*.

- Choose z in the *Variable selector*.




Wrap By Scalar filter.

- Switch from 2D to 3D visualization in the *Layout Render view* to manipulate the project in 3D.



3D option.


- Remove the color map of the bed elevation z by selecting *Solid Color* in the *Coloring* drop-down menu of the *Properties* tab:



Coloring parameter.

- The *Solid Color* can be customized clicking the Edit color map icon 

in the *Properties* tab. Once the desired color has been chosen at the *Pick Solid Color tab* (this example uses HTML=#ecb57d), the *Render view* should look as:



3D bed elevation representation.

To view the terrain from different points, use the left mouse button to rotate, press down the mouse wheel to translate, and scroll the mouse wheel to zoom in or out the image.

Using the *Viewpoint Toolbar* (Figure 21.22), you can add different view points of your graphic clicking  .



Figure 21.16 – Viewpoint Toolbar.

The following image was generated using an alternative view point.




Figure 21.17 – Alternative 3D bed elevation representation.

To return to prearranged views use the *Camera control* toolbar.



Figure 21.18 – Camera Control Toolbar.

A more sophisticated visualization can include additional layers. In the next section we will add two more layers: the water elevation (h+z) and the velocity vector field.

21.3.1 Create a 3D water elevation graphic adding a (h+z) layer

Follow the following steps to create the (h+z) layer:

- Click on the *CellDataToPointData* item in the *Pipeline Browser* and select *Warp by Scalar* in *Filter/Alphabetical*. A *WrapByScalar2* item will be created in the *Pipeline Browser*.
- Select a time $\neq 0$ in the *Time control toolbar*, e.g. 

- Configure the *Properties* panel as follows:
  - Scalars = (h+z)
  - Scale factor = 25 (very important)
- Click the *Apply* button. Check that h is in the *Variable selector*.
- Click  and choose the *Rainbow Desaturated* color map, then *Apply/Close*.

The resulting Render view should look similar to:




Figure 21.19 – Water surface elevation representation.

As seen in this figure, the layers corresponding to z and (h+z) variables are overlapped in the dry areas of the domain, generating a confusing presentation. One easy way to fix this issue is to remove the water depth h values below a user-defined value to avoid overlapping, doing as follows:

- Click *WrapbyScalar2* in the *Pipeline Browser* and select *Threshold* in *Filter/Common* in the main menu

- Click *Apply* in the *Properties* panel, and check that h is in the *Variable selector*.

- Set the minimum value equal to 0.01 m. Depths (h) below this minimum will not appear in the color representation.

- Click *Apply* and the result should be as follows:




Figure 21.20 – Threshold Filter application.

With the *Threshold* layer selected, change the color map for water depth h to a white-to-blue as it was explained in Section 21.2.2 of this tutorial. The result graph should look as follows:




Figure 21.21 – Three dimensional water depth h representation.


21.3.2 Create a velocity field graphic

Follow the following steps to create a velocity field graphic:

- Select the *Threshold* item in the*Pipeline Browser*.
- In the Filters menu select *Common/Glyph* and click the *Apply*.

- Configure the *Properties* panel as follows:

  - Glyph type = *2D Glyph*
  - Orientation Array = velocity
  - Scale Array = modU (velocity modulus)
  - Scale Factor = 25
  - Glyph mode = *Every Nth Point* (to prevent a saturation of arrows in the visualization)
  - Click the *Apply* button to visualize immediately the filter setup, the user can press this button after each of the previous steps
  - Set Coloring as (modU) for the color map representation and choose the preset color Rainbow desaturated then *Apply/Close*



- Select Time $\neq 0$ as the current time control tool bar. In this example chose for instance *Time=3*.

After these steps, the graphic should look like this one:




Figure 21.22 – Three-dimensional velocity field representation.

In order to save this Paraview project select *File/Save State* and create a '.pvsm' file. To load any of the saved projects select *File/Load State* and select a '.pvsm' file.

21.4 Generating animations

With your Paraview project loaded in your computer to create an animation or movie go to *File/Save Animation* and create a file type '.avi'. The *Save Animation Options* dialog will be displayed:




Figure 21.23 – Animation.

In this dialog, the user can configure the video frame rate, the number of frames per time step, the resolution (in pixels) and the range of time steps. In order to reduce the size of the output video file, a compression mode is also available for the video. Note that this will also reduce the video quality of the animation. As an example, the next figures show three frames of the output video generated in this way, corresponding to six different simulation times.
Animation time frames.

21.5 Streamlines representation

Streamlines represent the instantaneous direction of the velocity and is drawn as unending lines that may converge or diverge from one another. They are drawn at roughly even intervals to capture the flow in all areas.

To create Streamlines with Paraview, follow these steps:

- Open the Paraview application in your computer
- Load the plugin *StreamLinesRepresentation* in *Tools/Manage Plugins* in the main menu
- Open the 'BridgeTutorial..vtk' Group file and Select *Apply*
- Select a time different than 0 in the time control tool bar
- Select velocity in the *Variable selector*
- In the *Properties* panel select:
  - Representation = StreamLines
  - Step Length = 1
  - Number of Particles = 1000
  - Max Time to Live = 600
- To have Streamlines in one color, select in the Property panel Coloring = *Solid* and then click on 

and select a color.

The next figure shows how the StreamLines look:




Figure 21.24 – StreamLines representation.

If you load a Paraview project '.pvsm' file, you have to deactivate the filters in the *Pipeline Browser* by clicking the open eyes so that only the '*.vtk' file layer is open.